



NARRATIVE

The purpose of this survey was to establish the boundaries of lots 11 thru 15 and the north one-half of lot 16, Block Two of Saling and Reese's Addition to the city of Weston. A 5/8" iron pin was found at the intersections of Main & Franklin streets which had been used in previous surveys. Concrete nails were found in the centerlines of Main and Broad and Hill streets. No record of these points could be found, however they do fit existing buildings and retaining walls, they were used for centerline control. Dimensions on the original plat were called for as being slope dimensions, however we used horizontal distances in this survey in order to conform to present day practices. Angles shown are as indicated on the original plat.

- denotes 5/8 in. x 30 in. iron pin with aluminum cap set
- denotes existing deciduous tree located at property corner
- denotes 5/8 in. iron pin found

RECEIVED BY

Umatilla County Surveyor
 Date 2-15-83
 Rec'd by B&L
 No. 83-18-A

REGISTERED
**PROFESSIONAL
 LAND SURVEYOR**
David H. Krumbein
 OREGON
 JULY 17, 1970
DAVID H. KRUMBEIN
 933

K KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon Survey for FETTERLY Lots 11, 12, 13, 14, 15, & N 1/2 16, Block 2 "Saling & Reese's Addition," Weston, Oregon	SCALE 1" = 50'
	DATE Dec. 7, 1982
	DRAWN BY M.L.D.
	CKD. BY D.H.K.
	DRAWG. NO. 82-318