



N 89° 47' 38" W 5281.40 Computed Don't use

SCALE: 1" = 200'

NARRATIVE: The purpose of this survey is to stake the west line of the W 1/2, SE 1/4 SW 1/4 Sec. 5 & to partition 2.0 Ac. out of the North part thereof. In 1975 Cris Palmer of Wayne Harris Co. supplied me with a Section Breakdown which was used in many surveys in sec. 5. I discovered an error in the location of the NE. Cor. of said section when surveys did not fit fences and road centerlines. I changed & set that corner in my 1975 sur. for Myrick.

Recently Walt Cramer has found Iron pipes at the NW & SW corners of said section 5 which are different from Palmers. Cramer thinks those pipes are Kimbrells. I used those pipes to partially resubdivide the section. I did not set the W 1/4 cor on line between said corners because it would not fall in the E of Canal Road. I split the tree & fence lines on Canal Road for the east position of said 1/4 cor. That location makes the surveyed N-S E of the SW 1/4 of the NW 1/4 and the N-S E of the NW 1/4 of the SW 1/4 fit old Tree & fence lines.

Description of 2.0 Ac. The North 263.00 feet of the NW 1/4 of the SE 1/4 of the W 1/2 of Sec. 5, T4N, R29E, W.M. UMATILLA CO., OR. May have to give easement over E. 25 FT of W 1/2 of SE 1/4 of SW 1/4 of S. Sec. 5.

Set 1/2" IR in Tree line in SE 1/4 of NW 1/4 NW corner touches Prop. line

REGISTERED PROFESSIONAL LAND SURVEYOR

D. Dennis Edwards

OREGON JULY 18, 1871 G. DENNIS EDWARDS 951

RECEIVED BY
Umatilla County Surveyor
Date 6-7-85
Rec'd By MLD
No. 85-15-A

SURVEY FOR ROBERT ATKINS
IN NW 1/4 Sec. 5, T4N, R29E, W.M. UMATILLA COUNTY, OREGON
5/10/85 Job # 58504021
EDWARDS SURVEYING P.O. Box 763
567-3336 HERMISTON, OR.

o 1/2" x 24" Iron Rod set with Alum tag stamped 951

85-65-A