

3 1/4" DIA. BRASS CAP  
MKD.: T55 R30E  
1/4  
S26 | S25  
1978

1/4  
26 | 25

1325.14'  
1325.14'  
N. 0° 01' 18" E., 2650.28'  
(610' NORTH, 40.00 ch)

SE 1/4 SE 1/4 SECTION 26  
U.S.

SW 1/4 SW 1/4 SECTION 25  
LOUISIANA-PACIFIC CO.

3 1/4" DIA. BRASS CAP  
MKD.: T55 R30E  
S26 | S25  
S35 | S36  
1978

26 | 25  
35 | 36

BASIS: SUNSHOT  
S. 15° W., 570' FROM  
SE COR. SECTION 26  
MAG. DECL. 19° E.



**LEGEND**

- FOUND BLM BRASS CAP MONUMENT, PROPERLY SET IN 1978.
- SET 2 1/2" x 30" ALUM. PIPE WITH 2 1/2" ALUM. CAP BY SURVEY MEASUREMENT; CERTIFIED RECORD OF CORNER MONUMENTATION WITH THIS PLAT.
- NATIONAL FOREST BOUNDARY POSTED.

**HISTORY AND NARRATIVE**

REFER TO: L-P COOP. SURVEY FOR THE U.S. FOREST SERVICE IN SECTION 26, T.5S., R. 30E., W.M., HISTORY AND NARRATIVE FILED WITH THIS PLAT.

L-P COOP. SURVEY FIELD NOTES, BOOK 1

**CERTIFICATE OF SURVEY**

I, FAYETTE S. MUNRO, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY THAT THIS PLAT AND THE HISTORY AND NARRATIVE HEREIN REFERRED TO ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED BY ME OR UNDER MY DIRECTION IN MAY, 1990, FOR THE U.S. FOREST SERVICE, IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND THE ARTICLES OF MY CONTRACT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Fayette S. Munro*

OREGON  
JULY 13, 1979  
FAYETTE S. MUNRO  
1832

*Fayette S. Munro*

FAYETTE S. MUNRO  
REGISTERED PROFESSIONAL LAND SURVEYOR  
OREGON LICENSE NO. 1832

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE THIS 4<sup>TH</sup> DAY OF JANUARY, 1991,  
*Dennis J. Floyd* C.O.R.

I CERTIFY THAT THIS SURVEY WAS PERFORMED AT THE REQUEST OF THE UMATILLA NATIONAL FOREST SUPERVISOR.

*D. Blackburn*  
SIGNATURE

1/4/98  
DATE

**PLAT OF L-P COOP. SURVEY FOR THE U.S. FOREST SERVICE**

SECTION 26, T.5S., R.30E., W.M., UMATILLA CO., OREGON

U.S.D.A. - FOREST SERVICE CONTRACT NO. 00-04R3-0-22

RECEIVED BY  
Umatilla County Surveyor  
Date 1-91  
Rec'd By KA  
No. 91-010-A

91-10-A

L-P Coop. Survey for the U.S.D.A. Forest Service  
Section 26, T.5S., R.30E., W.M.

HISTORY AND NARRATIVE

History

Frank W. Campbell subdivided T.5S., R.30E. under G.L.O. contract no. 468, dated April 12, 1883. He set the original corners on the east line of Section 26.

Craig L. Wanless, Cadastral Surveyor, under Special Instructions, Group No. 350, dated Mar. 27, 1978, remonumented the east  $\frac{1}{4}$  corner and the southeast section corner of Section 26 from original evidence.

Narrative

This survey was performed at the request of and under contract with the U.S.D.A. Forest Service in May, 1990. The purpose of the survey was to set the NE corner of  $SE\frac{1}{4}$   $SE\frac{1}{4}$  of Section 26, T.5S., R.30E., W.M. and to post forest boundary along the east line of that parcel.

The controlling corners were tied by a closed traverse and approved radial methods using a 10" theodolite and an infrared distance meter.

The S1/16 corner common to Sections 25 and 26 was monumented according to the Manual and the contract specifications.

Forest boundary was posted with 6' steel fence posts and Forest Service boundary signs.

Fayette S. Munro  
P.O. Box 242  
Pendleton, Or. 97801



RECEIVED BY

Umatilla County Surveyor

Date 7-91

Rec'd By LA

No. 91-010-A