



Map showing
 S.E/4 of Sec. 34, T. 35, R. 30 E. W.M.
 Part of Doherty Ranch.
 Surveyed - Oct 1952 - By W.E.O. Criger.
 Scale: 1" = 1 Mile.

4E-X5-Q-889Ax

To F. B. Hayes - Umatilla Co. Surveyor.
Memorandum - Field Notes -
For Doherty Estate - Gurdane - (and Vincent)

We set up over a stone set for the S.E. Corner of Sec. 34 - T. 3 S., R. 30 E. W. My which was referenced in from two Bearing trees.

Ran random line west 2654 ft. to a point $22\frac{1}{2}$ ft. south of the S/4 corner of Sec. 34 which was marked with a stake and stone and referenced in with 4 trees from the original U. S. Land survey.

We then corrected the back line to the S.E. Cor. of Sec. 34.

Then set up on the S/4 Cor. Stone and Ran. North 2652 ft. to the center of Sec. 34 where we set an Iron Pin.

Then ran S. $89^{\circ}45'E$. 6635 ft and set an iron pin to mark the N.E. Cor. of the W/2 of the W/2 of the S.E/4 of sec. 34; then continued S. $89^{\circ}45'E$. 19905 ft. to the E/4 Cor. of Sec. 34 where we placed an iron pin and found a stone.

Iron pins set at all 4 corners of the W/2 of the W/2 of the S.E./4 of Said Sec. 34.

October - 1952 -

By W. E. O. Criger and H. L. Melton. -

Note: the W/4 Cor. of Sec. 34 is marked with an Iron pin and the old original stone and four bearing trees.