

FIELD NOTES

"EKLEBERRY TRACTS"
Umatilla County, Oregon

Surveyed and platted by:
V.R. Fraley #183

The survey of Ekleberry Tracts coincides and is a part of my survey of Section 9, T. 4 N., R. 28 E., W.M. The field notes of which I filed with the Umatilla County Surveyor on July 10, 1950.

EXCEPTIONS I changed my true bearing of North $0^{\circ}-20'$ East to North in order to satisfy the Title Co. and to coincide with previous surveys of the vicinity. The bearing of North is what I finally used for the East line of Section 9, and made all lines in the section to coincide as to bearings. The length of the west line of the tract was changed from 641.18 to 641.02 by order of the Title Co.

TRAVERSE OF TRACT

North $89^{\circ}-09'$ West 33 feet from the N.E. Corner of the S.E. Quarter of the N.E. Quarter of Section 9, I planted a 6"x6"x24" concrete monument 6" below the surface of the ground for the Initial Point of the plat. I had previously bisected the N.E. Quarter of Sec. 9 according to law and had drove a $5/8$ " iron pin for the N.W. Corner of the S.E. Quarter of the N.E. Quarter. The length of the North line of the S.E. Quarter of the N.E. Quarter is 662 feet but I had to produce the line 16 feet further West in order to get enough length for the lots on the West side of the tract.

I ran the traverse on around the tract, making certain I checked into previous surveys of the Brace, Ryan and Leib tracts. I found wood hubs at the N.W. and N.E. Corners of the Brace Tract and used them in the survey.

Q-1328-Ap