



NARRATIVE

The purpose of this survey was to determine the boundaries of a parcel lying between the 'A' and 'C' Line Canals of the Hermiston Irrigation District. The 'A' Line Canal was established by tying the North edge of the concrete lining and going 30 ft perpendicular from there to establish the North right-of-way line. The 'C' Line Canal is essentially vacated and the centerline of the canal was tied. In checking with the County Assessor's office the 'A' Line Canal right-of-way was determined to be 50 feet either side of centerline in width.

G. Dennis Edwards survey for Realty World and Jerry Carr, Umatilla County Survey Records drawing no. S-33-AX was used to establish the North-South centerline of section 7.

Bearings are based on a survey by Krumbain Engineering, Ltd. for Umatilla County, dated July 18, 1980.

CURVE DATA

No.	Radius	Arc	Chord	Chord Bearing
1	48.02	40.30	39.13	S64°15'31"W
2	326.19	146.86	145.62	S75°24'03"W
3	554.39	138.33	138.57	S69°40'30"W
4	343.45	147.80	146.76	S64°30'36"W
5	98.02	34.49	34.31	S78°13'12"W
6	276.19	124.35	123.30	S75°24'03"W
7	604.99	151.45	151.06	S69°40'30"W
8	293.45	126.36	125.39	S64°30'36"W

- denotes Brass Cap found, set by Wayne O. Harris, November 1968, for Turn-a-Lum Lumber
- denotes 1/2 in. x 30 in iron pipe with 2 1/2 in. Brass Cap set.
- denotes 3/8 in. x 30 in iron pin with aluminum cap set
- denotes 1/2 in iron pin found, set by G. Dennis Edwards, March 3, 1981 for Realty World and Jerry Carr, Umatilla County Survey Records drawing no. S-33-AX
- denotes posts from old fence

RECEIVED BY
 Umatilla County Surveyor
 Date 6-5-82
 Rec'd by BLS
 No. 82-42-A

David H. Krumbain

Revised December 23, 1981-MH

KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon	SCALE 1"=100'
	DATE Dec 17, 1981
Survey for BURNETT-MCKITRICK	
located in NE 1/4 of Section 7, T41N, R29E, W11E	
DRN. BY RDR	DATE 8-23-80
CHKD BY D.H.K.	