



NARRATIVE OF SURVEY
 THIS SURVEY INVOLVED PARTIAL SUBDIVISION OF SECTION 34, T35 R31E, W.M. AND ESTABLISHING, RE-ESTABLISHING, OR RE-MONUMENTING CERTAIN CORNERS IN SECTION 2, T45, R31E, W.M. AFTER LOCATING EVIDENCE AND MEASURING BETWEEN EACH REQUIRED CORNER, SECTION 34 WAS SUBDIVIDED AS SHOWN ON THIS MAP BASED ON THE MANUAL OF INSTRUCTIONS. THE LOST N 1/4 CORNER OF SECTION 2 WAS RE-ESTABLISHED ON THE SOUTH LINE OF SECTION 34 BY SINGLE PROPORTIONATE MEASURE BETWEEN THE S 1/4 AND THE SOUTHWEST CORNER OF SECTION 34. THE E 1/6 OF SECTION 2 WAS ESTABLISHED ON THE SOUTH LINE OF SECTION 34, MIDWAY BETWEEN THE RE-ESTABLISHED N 1/4 CORNER OF SECTION 2 AND THE NE CORNER CORNER OF SECTION 34. MEASUREMENTS WERE MADE BY RANDOM CLOSED TRAVERSE WITH 1" THEODOLITE AND INFA-RBO DISTANCE MEASURING EQUIPMENT. THE SOUTH LINE OF TOWNSHIP 5 SOUTH RANGE 31 EAST, W.M. WAS ORIGINALLY SURVEYED BY GEORGE S. PERSHIN UNDER CONTRACT NO. 304 DATED SEPTEMBER 19, 1878. THE NORTH, EAST AND WEST LINES OF SECTION 34, TOWNSHIP 5 SOUTH, RANGE 31 EAST WERE ORIGINALLY SURVEYED BY GEORGE S. PERSHIN UNDER CONTRACT NO. 319 DATED MARCH 26, 1879. THE NORTH LINE OF TOWNSHIP 4 SOUTH RANGE 31 EAST, W.M. WAS ORIGINALLY SURVEYED BY GEORGE S. PERSHIN UNDER CONTRACT NO. 373 DATED SEPTEMBER 17, 1880.

REGISTERED PROFESSIONAL LAND SURVEYOR
 William R. Wells
 OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

NOTES
 ALL BEARINGS AND DISTANCES IN PARENTHESES ARE RECORD BEARINGS AND DISTANCES. FOR ADDITIONAL INFORMATION ON CORNERS RECOVERED OR MONUMENTED, SEE CERTIFIED RECORD OF LAND CORNER MONUMENTATION FILED HERewith. FIELD BOOK REFERENCE - TRAVERSE BOOK #34 AND MONUMENTATION BOOK #1 & 2 OF THE RILEY CADASTRAL SURVEY.

- LEGEND**
- - SET 2 1/2" O.D. GALV. IRON PIPE 30" LONG WITH 2 1/2" BRASS CAP FROM EXISTING EVIDENCE.
 - - SET 2 1/2" O.D. GALV. IRON PIPE 30" LONG WITH 2 1/2" BRASS CAP BY TRAVERSE SURVEY.
 - ⊙ - FOUND BRASS CAP ON 2 1/2" IRON PIPE SET BY BLM FROM EXISTING ORIGINAL EVIDENCE.
 - ==== U.S. FOREST BOUNDARY - BOUNDARY POSTED
 - [123] MEASURED DISTANCE IN METERS.
 - ROADS OR FENCES ALONG TRAVERSE LINE.

SURVEYORS CERTIFICATION
 I, WILLIAM R. WELLS, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY THAT THIS PLAT, AND THE NOTES HEREON, OR ATTACHED, ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY DIRECT SUPERVISION DURING THE MONTHS OF JULY, AUGUST, SEPTEMBER, & OCTOBER 1982, FOR THE U.S. FOREST SERVICE, IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND WITH THE ARTICLES OF THE CONTRACT.
 William R. Wells
 WILLIAM R. WELLS, PLS
 OREGON LICENCE NO. 1106

WAILLUS PROJECT NO: 82-109	USFS CONTRACT NUMBER 55-CATS-22-01724 R6-14-82-710
PROJECT: RILEY '82 CADASTRAL SURVEY PERFORMED FOR US FOREST SERVICE UMATILLA NATIONAL FOREST	
SCALE 1"=500' DATE 11/2/82 DES BY: DR BY: WRW CK BY: WRW	TITLE: UMATILLA COUNTY T35 R31E, W.M. SEC 34 T45 R31E, W.M. SEC 2
REVISIONS	
DRAWN/RECEIVED BY Umatilla County Surveyor Date 12-82 Rec'd By BCS No. 82-138-B SHEET 1 OF 1	

also notes