



NARRATIVE

The purpose of this survey was to establish the boundaries of that parcel described on Page 330, Book 186 of the Deed Records of Umatilla County, Oregon. The description calls for a tie to Block 33 of the Town of Adams. We found monuments as found by Wayne O. Harris, Umatilla County Surveyor in 1978, and used old distances and bearings to establish the southwest corner of Block 33. There is one call in the description to the East line of the County Road, it was presumed that the intent was to front the County Road for the entire parcel. Wildhorse Creek has moved since 1906 and the distances shown are as they existed on October 4, 1982.

Bearings are based upon a survey by Wayne O. Harris, Umatilla County Surveyor in 1978, Umatilla County Survey Records drawing no. Q-1122-C.

- denotes monument found
- denotes 5/8in. x .30in. iron pin with aluminum cap set

CURVE DATA

No.	Radius	Arc	Chord	Chord Bearing
1	1820.00	209.66	205.55	1121°58'48"E
2	1820.00	271.25	271.00	117°28'23"E

RECEIVED BY
 Umatilla County Surveyor
 Date 2-15-83
 Rec'd By B&C
 No. 83-09-B

REGISTERED PROFESSIONAL LAND SURVEYOR
 David H. Krumben
 221 S. Main, Pendleton, Oregon

KRUMBEIN ENGINEERING CO.
 ENGINEERS - SURVEYORS - PLANNERS
 221 S. Main, Pendleton, Oregon

SCALE 1"=100'
 DATE October 11, 1982
 DRN. BY MAI
 CKD BY D.H.K.
 DRNG. NO. 82-34C

located in Section 9, T.3.N., R.34.E., W.M., Adams, Oregon
 Job No. 82-116