



**CURVE DATA**

No.	Radius	Arc	Chord	Chord Bearing
1	20.00	26.27	24.42	N74°34'23"W
2	175.00	33.94	33.89	N31°09'24"W
3	225.00	43.68	43.61	N31°09'24"W

**NARRATIVE**

The purpose of this survey was to divide Tract IV of "Michals Second Addition" to Milton City, Umatilla County, Oregon. The dividing lines were based upon a Preliminary Plat for a "Biloff's Second Addition" which was never completed. The City of Milton-Freewater acquired 1/2 feet off of the West line of said Tract IV for a street right-of-way. We tied to pins in "Jefferis's Second Addition," the southeast section corner and the East one-quarter corner of Section 12, Township 5 North, Range 35 East, W.M. and pins in "Biloff's First Addition" as shown.

Bearings are based upon the Plat of "Jefferis's Second Addition," to Milton City, Umatilla County, Oregon.

- denotes stone found, set 1 1/2 in x 30 in iron pipe with 2 1/2 in Brass Cap
- ⊙ denotes Brass Cap found
- denotes 5/8 in iron pin found
- ⊙ denotes 5/8 in x 30 in iron pin with aluminum cap set
- denotes P.K. nail set in concrete gutter
- ▬ denotes area dedicated to the public

RECEIVED BY  
 Umatilla County Surveyor  
 Date 2-15-83  
 Rec'd By BLC  
 No. 83-10-B

REGISTERED PROFESSIONAL LAND SURVEYOR  
 Daniel H. Kuhn  
 308 S. Main  
 Pendleton, Oregon

**KRUMBEIN ENGINEERING CO.**  
 ENGINEERS - SURVEYORS - PLANNERS  
 221 S. Main, Pendleton, Oregon

SCALE 1"=50'  
 DATE October 12, 1982  
 DRN. BY MI  
 CKD. BY DAK  
 DRNG. NO. 82-35C

Survey for  
**MILAN SMITH**  
 located in Sections 12 & 13, T5N, R35E, W.M.  
 Tract IV, "Michals Second Addition" to Milton City, Ore.