



NARRATIVE:

The purpose of this survey was to locate the boundaries of the Woodhall property as recorded on Roll 100, Page 2129 of the Umatilla County Deed Records, and to divide said property into three tracts. Bearings were based on a survey by Krumbain Eng. for Sams-Corey dated 11-5-75, Umatilla County Surveyor Drawg. No. J-152-A. Since no local control could be found we used the existing North-South running fence lines as the extreme property line as the distance between them fit the legal description as did the location of the fences in location to the rock bluff and the canyon in the bluff mentioned in the legal description. Ties to the prior survey mentioned previously and a fence corner lying in approximately the Northwest corner of Section 25 confirm the fence line on the West side to be the section line.

• denotes set 3/8"x30" iron pin with aluminum cap stamped PLS 933

	KRUMBEIN ENGINEERING LTD ENGINEERS - SURVEYORS - PLANNERS 361 S E Second Pendleton, Oregon		Scale 1"=200'	Dwn. By MLD	Dwg. No. 84-15C	Revision 1 4-28-04
			Date 3-28-04	Ckd. By DMH	Job No. 84-36	Revision 2
Survey for WOODHALL Section 25, T5N, R36E, W1M.		David H. Krumbein		5/30/04 he no. 84-152-8		