



NARRATIVE:

The purpose of this survey was to partition out two parcels from that tract of land belonging to Vern Coee located in the NE 1/4 of the SW 1/4 of Section 11, T2N, R33E, W.M., as recorded in Book 258, Page 348 and Book 313, Page 199 of the Umatilla County deed records.

The property was originally to be the East 32 acres of the Northeast quarter of the Southwest quarter. Using the Wallulis & Associates Survey, County Surveyor No. 82-60-B, for the Umatilla Reservation Housing Authority, we established the boundaries of this 32 acres which fit well with the found witness cap for the NE corner of the Indian Reserve.

Parcels were sold off the original 32 acres until there remains 22.6 acres. Reference deeds noted above.

Bearings are based on the centerline of Section 11 bearing N 89°59'38\"/>

- denotes set 9/8\" x 30\" iron pin with aluminum cap stamped PLS 933
- ▼ denotes find 1\" dia. aluminum cap, Co. No. 82-60-B by Wallulis
- denotes find R/R Spike, Co. No. 82-60-B
- denotes NE corner of Indian Reserve
- denotes witness cap 50 ft South and 30 feet West of Indian Reserve NE corner

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 381 S.E. Second Pendleton, Oregon	Scale 1"=100'	Dwn. By MLD	Drng. No. 85-610	Revision 1
	Date 11-7-85	Ckd. By DHL	Job No. 85-132	Revision 2
Survey for CASE		RECEIVED BY Umatilla County Surveyor Date <u>1-10-86</u> Rec'd By <u>[Signature]</u> No. <u>86-4-B</u>		
SW 1/4, Sec 11, T2N, R33E, W.M.				