

**NARRATIVE**


The purpose of this survey was to establish the westerly line of that tract of land conveyed and recorded on Roll 132, Page 442 of the Umatilla County Deed Records, said tract lying within Block 14 of the Riverside Addition to the City of Milton-Freewater.

Many unrecorded monuments were located and ties were made. After plotting and comparing improvements and points shown on a 1947 survey by Robnett and a survey for the City of Milton-Freewater by McInd, I accepted the locations of the monuments noted as #1, #2, #4, from which by projection verified the location of pin #5 as being correct.

Bearings are based upon River Street bearing North 0° East as shown on the Plat of Riverside Addition and the 1947 survey by Robnett, County Surveyor No. 5-156-B.

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PL5 933
- denotes fnd 3/8" iron pin stamped PL5 933 used for Wrinkle Survey
- denotes fnd 1/2" iron rod as noted
- ▽ denotes fnd 5/8" iron pin with State Hwy aluminum cap set as traverse point not as a right-of-way
- denotes fnd R/R spike
- denotes fnd 2" steel shaft w/1/2" bevel gear
- ▼ denotes fnd Pk nail
- ▽ denotes fnd concrete nail
- denotes fnd 1/2" iron pin stamped PL5 933 used for Wrinkle Survey

**DETAIL NO. 1**  
115



R/R spike set by McInd in 1981 for Twin Village Cable TV

<b>KRUMBEIN ENGINEERING LTD.</b> ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=30'	Drn. By MLD	Orig. No. 87-090	Revision 1
	Date 6-26-87	Chk. By DJA	Job No. 87-12	Revision 2
Survey for <b>GOODWIN</b>		RECEIVED BY Umatilla County Surveyor Date 6-28-88 Rec'd by JA No. 88-318		
NE 1/4, SE 1/4, Sec 12, T5N, R35E, W.1.				