



NARRATIVE:

The purpose of this survey was to partition out parcels of land from that tract of land belonging to Jack Sweet in Section 21, T2N, R3E, W1M. This property is bounded on the East by U.S. Highway 395 and was shown on a survey by Krumbein Eng Co for Jim Farley, Umatilla County No. U-60-B and is also shown on a survey by Wallulis & Associates for PP&L, Co. No. R-178-B. The South line of the parcel was established by Umatilla County Surveyor No. U-60-B, pins were found as shown. The West line is established by the centerline of McKay Creek and the North-South centerline of the South Part of Section 21, which was broken down in Umatilla County Surveyor No. U-60-B. The North line of the parcel was also established in County Surveyor No. U-60-B. Bearing base and control for this survey was the Wallulis survey for PP&L, Co. No. R-178-B.

- denotes set 3/8"x30" iron pin with aluminum cap stamped PLS 933
- denotes 1/2" 5/8" iron pin, Co. No. R-178-B
- denotes 1/2" 3/8" iron pin, Co. No. H-137-A
- denotes 1/2" 3/8" iron pin, Co. No. U-60-B
- denotes 1/2" Brass Cap, Co. No. U-60-B
- denotes 1/2" iron pin, OSHD

Jim Gugir
R.53, Page 947

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon		Scale 1"=100' Date 7-18-86	Dwn. By MLD Ckd. By DMS	Dwg. No. 85-65C Job No. 25-447	Revision 1 Revision 2
Survey for SWECK		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbein</i> DAVID H. KRUMBEIN 933		8-90 90-55B	

SE4, Sec 21, T2N, R3E, W1M.