



**SECTION 32 T.4N, R.37E.W.M.**  
**NARRATIVE**

1. Found 5/8" iron pin w/aluminum cap mkd 1/16 set by Krumbein 1981 county drawing S-154
  2. Found brass cap marked T4N, R37E and SW 1/4 S 32 bearing trees, set by Krumbein 1981 County drwp. S-104-B
  3. Found 2" pipe set by Streamer 1974 County drwp. L-55-B Used by Krumbein in 1981 county drawings S-104-B & S-154
  4. Set 3/4" x 30" iron pipe tagged LS 1341 1/16. Location determined from Krumbein surveys County drwp. S-104B and S 154.
  5. Set 3/4" x 30" iron pipe tagged LS 1341
  6. Set 3/4" x 30" iron pipe tagged LS 1341 Mkd C 32-4-37 1991
- Location determined as in #4.
7. Bearings based on Krumbein surveys in 1981. S-104-B & S 154.
  8. Lines staked to conform to land trade between property owners.
  9. Distances and bearings measured in the field checked with those of county surveys S 104B & S 154. Distances and bearings shown are as measured in the field and are identical to the referenced surveys.
  10. Extended south from found East line of NW 1/4, SE 1/4, NW 1/4 to set SE corner SW 1/4, SE 1/4, NW 1/4 at given distance on Survey S 154. Random line to West 1/4 corner of section to determine line and bearing. Distance agreed with Survey S 154 & S 104B; therefore, set SE corner SW 1/4, NW 1/4 at distance called out on referenced surveys. Turned angle and proceed South to points on West portion of NW 1/4 of SW 1/4 set by turning angle at NW 1/4 corner of section on Survey S 104B and setting lines parallel to section lines - SE corner of SW 1/4 of NW 1/4 and projecting distance of Survey S 154.
  11. Distances and bearings marked E 3 were set in field but reflect information shown on referenced drawings.
  12. Deed references: R 16 page 1194 & Book 244 page 393.

**SURVEY FOR**  
**OREGON INSTITUTE FOR REHABILITATION, RESEARCH AND RECREATION, INC.**  
 N. 1/2 SW 1/4 Sec. 32 T.4N, R.37E.W.M.  
 SCALE 1"=500'

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
 Gary W. Streamer  
 BERTHOUD, OREGON  
 CITY OF WALLA WALLA

May 30, 1991  
 930 Home St.  
 Walla Walla, Wa 99362

RECEIVED BY  
 Corvallis County Surveyor  
 Date: 6-9-92  
 Rec'd by: KK  
 92-90-B