



LEGEND

- - SET 5/8" BY 30" IRON PIN WITH 1/2" YELLOW PLASTIC CAP MARKED FOR PLS 1106 MA PLS 11312.
- - MONUMENT FOUND AS NOTED.
- (XXX) - RECORD DIMENSIONS, RESERVE ADDITION PLAT.
- - EXISTING FENCE LINE.
- ④ - LOT NUMBERS, BLOCK 158, RESERVE ADDITION.

NARRATIVE OF SURVEY

THIS SURVEY WAS MADE AT THE REQUEST OF MIKE WISTER, TO LOCATE AND MONUMENT BOUNDARIES OF LOT 3, BLOCK 158, RESERVE ADDITION, PENDLETON, OREGON. CONTROLLING MONUMENTS ARE SHOWN. THE LOT PERIMETER WAS LAID OUT BY RECORD ANGLE AND DISTANCE USING RESERVE ADDITION MONUMENTS NO. 8 & 14 FOR CONTROL.

THIS SURVEY WAS MADE WITH A 2 PERSON CREW USING A LIETZ SET 3 B AUTOMATIC ONE SECOND TOTAL STATION. THE SURVEY WAS MADE BY A COMBINATION OF CLOSED TRAVERSE AND OPEN FIELD TRAVERSE WITH RADIAL TIES, WITH ANGLES AND DISTANCES DOUBLED WHEN MEASURING TO CONTROLLING CORNERS AND SETTING MONUMENTS.

RECEIVED BY
Umatilla County Surveyor
Date: 2-95
Rec'd by: KK
No.: 95-19-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
RENEWS 8/30/96

WILLIAM R. WELLS, PLS
357 N.E. HWY. 11
P.O. BOX 1696
PENDLETON, OR 97801
PHONE: (503) 276-6362

DATE: 12/15/94 DR BY: DMT
CK BY: WRW NO: 94-274

PROJECT:
SURVEY FOR:
MIKE WISTER
OF LOT 3, BLOCK 158,
RESERVE ADDITION,
PENDLETON, OREGON.
LOCATED IN THE NW 1/4, SECTION
12, T2N, R32E, 14M, UMATILLA
COUNTY, OREGON.

W18TER