



**SURVEY LOCATION**

SECTION 24, T4S, R30E., W.M., UMATILLA COUNTY  
SCALE: 1 INCH = 2500 FEET

**NARRATIVE OF SURVEY**

THIS SURVEY WAS MADE FOR THE PURPOSE OF MONUMENTING AND POSTING THE NORTH AND EAST LINES OF THE SOUTHEAST 1/4 OF THE SOUTHWEST 1/4 SECTION 24, T4S., R30E., W.M.

IN 1981, SECTION 24 WAS PARTIALLY SUBDIVIDED BY DOUGLAS M. FERGUSON, LS 848, AS SHOWN ON SURVEY NUMBER 82-1-C, RECORDED IN THE OFFICE OF THE UMATILLA COUNTY SURVEYOR. THE PRESENT SURVEY USED RECOVERED OR ESTABLISHED CORNERS FROM SURVEY NUMBER 82-1-C FOR CONTROL. BECAUSE OF CLOSE AGREEMENT WITH MEASUREMENTS SHOWN ON SURVEY NO. 82-1-C, CORNER POSITIONS WERE DETERMINED WITHOUT COMPLETELY RESURVEYING THE SECTION. BASIS OF BEARING FOR THE PRESENT SURVEY IS AS NOTED.

SURVEY MEASUREMENTS WERE MADE WITH A SOKKIA SET 4B 5 SECOND TOTAL STATION BY A COMBINATION OF CLOSED CONTROL TRAVERSE AND RADIAL TIES. CORNER MONUMENTS TIED AND MONUMENTS ESTABLISHED BY RADIAL METHODS WERE VERIFIED BY SEPARATE OBSERVATIONS.

**LEGEND**

- - SET 5/8" X 30" IRON PIN WITH 1/2" YELLOW PLASTIC CAP MARKED "PLS 1639".
  - - FOUND 3" BRASS CAP FROM SURVEY NO. 82-1-C, DATED 1981.
  - ⊕ - CALCULATED POINT ONLY, NOT SET OR FOUND.
- (XOX)RI - RECORD BEARING AND DISTANCE FROM SURVEY NO. 82-1-C, DATED 1981.

VGRANGER

RECEIVED BY  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
  
*William L. Hanley*  
 OREGON  
 JULY 14, 1978  
 WILLIAM L. HANLEY  
 1639  
 RENEWS 6/30/97

WILLIAM R. WELLS, PLS  
 357 N.E. HWY. 11  
 P.O. BOX 1696  
 PENDELTON, OR 97801  
 PHONE: (503) 276-6362  
 DATE: 11/21/95 DR. BY: DHT  
 CK. BY: JLNH NO: 45-347

PROJECT:  
 SURVEY FOR:  
**FOREST RECOVERY  
 INC.**  
 LOCATED IN THE S 1/2 OF  
 SECTION 24, TOWNSHIP 4 SOUTH,  
 RANGE 30 EAST, W.M., UMATILLA  
 COUNTY, OREGON.