



SCALE: 1" = 30'
 NORTH BASED ON PLAT OF
 WEST SLOPE PARK ADDITION

NARRATIVE

THE PURPOSE OF THIS SURVEY WAS TO FIND OR ESTABLISH THE CORNERS OF LOT 13 BLOCK 3 OF WEST SLOPE PARK ADDITION. I FOUND AND HELD THE MONUMENTS AT THE NORTHEAST AND SOUTHEAST CORNERS OF LOT 13. I FOUND MONUMENTS ON THE CENTERLINE OF SOUTHWEST 2ND STREET AS SHOWN. I HELD THE RADIUS AND ESTABLISHED THE CURVE BY HOLDING THE TANGENT LINES DEFINED BY THE FOUND MONUMENTS. I ESTABLISHED THE CURVE POINTS ON THE WESTERLY BOUNDARY OF LOT 13 BY HOLDING THE RADIUS AND THE RADIUS POINT DEFINED BY THE CENTERLINE MONUMENTS. I PROPORTIONED THE NORTHWEST AND SOUTHWEST CORNERS OF LOT 13 BASED ON CENTERLINE TANGENT DISTANCES.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

 OREGON
 JULY 30, 1978
 DAVID K. BATEMAN
 1088
 RENEWS 12-31-97

REPORT: 1 OF 1
 DRAWN: JDP
 DATE: 8/22/96
 SCALE: 1" = 30'
 FILE: O:\ANTH0001\LOT13BDY.DWG

REVISIONS

BOUNDARY SURVEY FOR
 SAINT ANTHONY HOSPITAL
 LOT 13, BLOCK 3, WEST SLOPE PARK ADDITION
 LOCATED IN THE SW 1/4 SEC. 11, T.2N., R.32E., W.M.,
 UMATILLA COUNTY, OREGON

DAVID EVANS AND ASSOCIATES,
 709 NW WALL STREET, SUITE 102 BEND, OREGON 97701



RECEIVED BY
 Umatilla County Surveyor
 8/30/96

 No. 96-142-B

(541)385-7614