



BASIS OF BEARINGS:  
BEARINGS WERE ROTATED TO GEODETIC NORTH  
ABOUT THE WEST 1/4 CORNER OF SECTION 21.

**LEGEND**

- - SET A 5/8" X 24" IRON PIN WITH 2" ALUMINUM CAP.  
SEE ACCOMPANYING CORNER CERTIFICATE.
- - FOUND MONUMENT AS NOTED.
- ⊕ - SET A 5/8" X 30" IRON PIN WITH 1 1/2" YELLOW PLASTIC CAP  
MARKED TOPPLS 1106, 1107, 118721.  
SEE ACCOMPANYING CORNER CERTIFICATE.
- ⊕ - CALCULATED POINT ONLY, NOT SET OR FOUND.
- - PROPERTY BOUNDARY POSTED WITH STEEL FENCE POSTS.
- (XX)R1 - RECORD BEARINGS AND DISTANCE FROM GLO SURVEY BY  
GEORGE S. PERSHIN, GLO CONTRACT NO. 319, DATED MARCH  
26, 1879.
- (XX)R2 - RECORD BEARING AND DISTANCE FROM SURVEY NO. 0-4-C.
- (XX)R3 - RECORD BEARING AND DISTANCE FROM SURVEY NO. 83-144-A.

**NARRATIVE OF SURVEY**

THIS SURVEY WAS MADE AT THE REQUEST OF FOREST RECOVERY, INC. TO LOCATE AND MONUMENT PROPERTY BOUNDARIES AND TO POST THE NORTH, WEST AND SOUTH LINES OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 21.

SURVEY MEASUREMENTS WERE MADE WITH A LEITZ SET 3 B ONE SECOND TOTAL STATION BY A COMBINATION OF CLOSED CONTROL TRAVERSE AND RADIAL TIES. CORNER MONUMENTS TIED AND MONUMENTS ESTABLISHED BY RADIAL METHODS WERE VERIFIED BY SEPARATE OBSERVATIONS.

CONTROL TIES TO THE WEST 1/4 CORNER, NORTH 1/4 CORNER AND EAST 1/4 CORNERS WERE MADE BY TOTAL STATION FROM STATIC GPS CONTROL POINTS ESTABLISHED NEAR EACH OF THE CORNERS.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

RENEWS: 6/30/98

RECEIVED BY  
The State Surveyor  
DATE: 5-97  
BY: KK  
NO. 97-1045-B

WILLIAM R. WELLS, PLS  
357 N.E. HWY. 11  
P.O. BOX 1696  
PENDLETON, OR 97801  
PHONE: (541) 276-6362

PROJECT:  
BOUNDARY SURVEY FOR:  
FOREST RECOVERY, INC.

DATE: 05/15/97 DR. BY: DMT  
CK. BY: WRN NO: 97-448

LOCATED IN THE SOUTHWEST QUARTER OF  
SECTION 21, TOWNSHIP 3 SOUTH, RANGE  
31 EAST, WM, UMATILLA COUNTY, OREGON.

VCARNEY