



BASIS OF BEARINGS
 THE LINE BETWEEN (1000) AND (1002) BEARS NORTH 89°35'15" WEST THE RECORD BEARING PER PP 2002-28 AND PP 2005-16.

NARRATIVE
 THE PURPOSE OF THIS SURVEY IS TO RESTORE MONUMENTS ALONG THE EAST LINE OF PARCEL 2, OF PARTITION PLAT 2005-16, WHICH WERE DESTROYED DURING INSTALLATION OF UNDERGROUND UTILITIES.

MONUMENTS WERE SET AS SHOWN HEREON AT THE PREVIOUSLY TIED OR SET POSITIONS AS LOCATED BY ME IN THE SURVEY FOR PP 2005-16.

LEGEND

- INDICATES FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP MARKED 'RS-GW 02817L5' PER PP 2002-28. 'H.E.L.D.'
- INDICATES SET 5/8" x 30" REBAR WITH YELLOW PLASTIC CAP MARKED 'E. NICLEY 54725L5' IN PLACE OF PREVIOUSLY TIED OR SET MONUMENT.
- ⊗ INDICATES MONUMENT FOUND 5/8" x 30" REBAR WITH YELLOW PLASTIC CAP MARKED 'E. NICLEY 54725L5' FROM PP 2005-16.
- () INDICATES RECORD INFORMATION PER PP 2002-28.
- NO () INDICATES MEASURED VALUE THIS SURVEY AND RECORD VALUE PER PP 2005-16.

CURVE TABLE

NUM	DELTA	ARC	RADIUS	BEARING	DISTANCE
C1	19°14'45"	188.29'	560.55'	S15°43'00"E	187.41'
C2	9°03'16"	88.58'	560.55'	S29°52'01"E	88.49'
C3	28°18'01"	276.88'	560.55'	S20°14'38"E	274.07'
C4	11°26'40"	431.96'	2162.54'	N28°39'18"W	431.24'

PRINTED WITH AN HP 110 PLUS PLOTTER WITH HP C4844A CARTRIDGE ON JPC 4M2 MYLAR

THESE 2 MONUMENTS SHOWN AS TIED WITH MY PRIOR PARTITION SURVEY. NOT REVISITED WITH THIS SURVEY.

SURVEY FOR:
**Hermiston
 Jehovah's Witnesses**
 Parcel 2, of
 Part. Plat 2005-16
 NW 1/4, Section 2, T4N, R28E, W1M,
 City of Hermiston, County of Umatilla, Oregon

SURVEY BY:
**Eathan Nicley
 Land Surveyor**
 161 130TH PL
 SOUTH BEACH, OREGON
 97136
 541-867-6649

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Eathan D. Nicley
 OREGON
 FEBRUARY 08, 2000
 EATHAN D. NICLEY
 54725L5
 RENEWAL DATE: DEC. 31, 2006

FIELD:	DRAWN BY:	EQUIP.	RAW FILE:	FIELD BOOK:	JOB NO.:	NO.:	DATE:
EDN\TM	EDN	GTS 302	Hermiston.raw	B 3, P 43			12/25/05

RECEIVED BY
 Umatilla County Surveyor
 Date: 2-06
 Received by: [Signature]
 No. 06-28-B