



SET 1/2" X 30" SQUARE IRON ROD WITH 1 1/2" ALUM. CAP MARKED "ODOT NW", FLUSH WITH GROUND.

SET 1/2" X 30" SQUARE IRON ROD WITH 1 1/2" ALUM. CAP MARKED "ODOT NE", UP 0.1' ABOVE GROUND, NEAR N-S FENCE LINE.

FOUND BEARING TREE, 28" DIAM. PONDEROSA PINE, WITH TAG AND HEALED BLAZE

FOUND BEARING TREE, 34" DIAM. PONDEROSA PINE, WITH BLAZE AND FENCE CONNECTED.

CABLE\_NW4  
N. 552,733.92  
E. 8,628,803.35  
(10/28/2011)

CABLE\_NE4  
N. 552,857.60  
E. 8,634,100.78  
(10/28/2011)

(QUARTER CORNER NOT SEARCHED FOR)

SECTION 33, T. 4 S., R. 32 E. W.M.

SECTION 4, T. 5 S., R. 32 E. W.M.

THE BEARINGS SHOWN ARE BASED UPON A SILVA HAND COMPASS. DECLINATION=17.5° EAST OF NORTH.

THE BEARINGS SHOWN ARE BASED UPON A SILVA HAND COMPASS. DECLINATION=17.5° EAST OF NORTH.

SET 32" PIPE WITH 1 1/2" DIAM. BRASS CAP STAMPED

SET 3/4" X 30" REBAR WITH 3/4" DIAM. ALUM. CAP STAMPED

OREGON DEPARTMENT OF TRANSPORTATION  
T4S R32E  
S32 S33  
S5 S4  
T5S R32E  
2011  
PLS 2613

MONUMENT SET 17.82' N. 52° W. FROM BEARING TREE AND PLACED 6" DEEP IN DIXIE RANCH ROAD.(TO TOP)

T4S R32E  
S33 S34  
S4 S3  
T5S R32E  
2011  
PLS 2613

FND 16"x10"x4" BASALT STONE. PLACED STONE ALONG SOUTH SIDE OF MONUMENT. PLACED ROCK MOUND AROUND MONUMENT.

SCRIBED NEW BEARING TREE, 18" DIAM. PINE. SCRIBING READS: "T 5 S R 32 E S5 BT". PLACED SECTION CORNER TAG ON TREE, PAINTED BLAZE RED WITH RED RING.

FOUND BEARING TREE, 32" DIAM. PONDEROSA PINE, WITH SCRIBING FULLY INTACT. SCRIBING READS: "T 5 S"

FOUND STUMP, WITH BLAZE AND SCRIBE MARKS

FOUND BEARING TREE, 28" DIAM. PONDEROSA PINE, WITH TAG AND VISIBLE SCRIBE. SCRIBING READS: "R 32 E S3"

PLSS REMONUMENTATION NOTES

1) THE NORTHEAST CORNER OF SECTION 4, TOWNSHIP 5 SOUTH, RANGE 32 EAST, W.M. WAS SET BY GEORGE S. PERSHIN IN MAY, 1881, CONTRACT NO. 390. THE G.L.O. NOTES STATE THAT PERSHIN SET A BASALT STONE 16 INCH X 10 INCH X 4 INCH FOR THE CORNER. FOUR BEARING TREES WERE SCRIBED: A PINE 6 INCHES IN DIAMETER, NORTH 38° EAST 123 LINKS, A PINE 6 INCHES IN DIAMETER, SOUTH 74° EAST 133 LINKS, A PINE 5 INCHES IN DIAMETER, SOUTH 38° WEST 110 LINKS, AND A PINE 5 INCHES IN DIAMETER, NORTH 18° WEST 122 LINKS. VISITING THE SITE, THREE BEARING TREES WERE RECOVERED. A STUMP WAS FOUND SOUTHWEST OF THE CORNER. A BLAZE WITH SCRIBE MARKS WAS FOUND IN THE STUMP. A 16 INCH X 10 INCH X 4 INCH BASALT STONE WAS FOUND BY MEASURING THE RECORD DISTANCES FROM THE THREE BEARING TREES. THE FOUND STUMP WAS APPROX. 2' OFF RECORD DISTANCE. A 32" PIPE WITH 2 1/2" DIAM. BRASS CAP WAS SET 25" IN GROUND FOR THE CORNER. THE FOUND STONE WAS PLACED ALONG SOUTH SIDE OF MONUMENT. A ROCK MOUND WAS PLACED AROUND MONUMENT. THE CORNER IS 46' NORTH OF EAST-WEST FENCE AND 22' WEST OF SEASONAL CREEK.

2) THE NORTHWEST CORNER OF SECTION 4, TOWNSHIP 5 SOUTH, RANGE 32 EAST, W.M. WAS ALSO SET BY GEORGE S. PERSHIN IN MAY, 1881, CONTRACT NO. 390. THE G.L.O. NOTES STATE THAT PERSHIN SET A PINE POST FOR THE CORNER. FOUR BEARING TREES WERE SCRIBED: A PINE 8 INCHES IN DIAMETER, NORTH 38° EAST 38 LINKS, A PINE 8 INCHES IN DIAMETER, SOUTH 52° EAST 27 LINKS, A PINE 8 INCHES IN DIAMETER, SOUTH 53° WEST 22 LINKS, AND A PINE 5 INCHES IN DIAMETER, NORTH 38° WEST 14 LINKS. VISITING THE SITE, ONE BEARING TREE WAS RECOVERED SOUTHEAST OF THE CORNER LOCATION. NO EVIDENCE OF THE CORNER WAS FOUND. THE POSITION OF THE SECTION CORNER WAS RE-ESTABLISHED BY MEASURING THE RECORD DISTANCE AND BEARING FROM THE EXISTING BEARING TREE. A 3/4" X 30" REBAR WITH 3/4" DIAM. ALUM. CAP WAS SET FOR THE CORNER. THE CORNER WAS PLACED 6" DEEP IN DIXIE RANCH ROAD. THREE NEW ACCESSORIES WERE SET: A 1/2" X 30" SQUARE IRON ROD WITH 1 1/2" ALUM. CAP MARKED "ODOT NE" BEARS NORTH 48° EAST 41.57 FEET, A PINE 18 INCHES IN DIAMETER WAS SCRIBED AS NOTED BEARS SOUTH 75° WEST 17.60 FEET, AND A 1/2" X 30" SQUARE IRON ROD WITH 1 1/2" ALUM. CAP MARKED "ODOT NW" BEARS NORTH 47° WEST 23.54 FEET.



LEGEND	
( ) RECORD DATA PER ORIGINAL GLO NOTES	RIGHT-OF-WAY
● SET MONUMENT	POINT NO. (2007)
★ SET GPS STATION	EXISTING CENTER LINE
	CORNER ACCESSORY

REGISTERED PROFESSIONAL LAND SURVEYOR  
*Mark D. Filsinger*  
OREGON  
JULY 20, 1993  
MARK D. FILSINGER  
2613  
EXPIRES: 12/31/2013

4

CABLE CREEK QUARRY

UKIAH - HILGARD HIGHWAY  
STOCKPILE AREA

CABLE OI  
SET 8" NAIL  
N. 548,514.21  
E. 8,633,525.34

RECEIVED BY  
Umatilla County Surveyor  
Date: 3/9/2012  
Rec'd By: *[Signature]*  
No.: 12-023-B

OREGON DEPARTMENT OF TRANSPORTATION  
CORNER RE-ESTABLISHMENT  
NORTHWEST CORNER AND  
NORTHEAST CORNER OF SECTION 4,  
TOWNSHIP 5 SOUTH, RANGE 32 EAST, W.M.  
UMATILLA COUNTY, OREGON  
ODOT REGION 5  
3012 ISLAND CITY AVE  
LA GRANDE, OR 97850  
FEBRUARY, 2012  
NO SCALE  
SHEET 2 OF 2