

# BASIS OF BEARING

True Geodetic North at the corner common to Section 33 and 34, Township 1 South and Section 3 and 4, Township 2 South, Range 36 East of the Willamette Meridian, as determined by GPS observation (NAD-83 (1991) datum)

SCALE: 1" = 500'

## LEGEND

- Found monument as noted, marked as per Umatilla County Monumentation Records
- ⊙ Set 2 1/2" x 30" Aluminum pipe with cap marked as per Umatilla County monumentation records, filed separately
- Set 5/8" x 30" rebar with 2 1/2" aluminum cap, marked as per Umatilla County monumentation records, filed separately
- [ ] Record measurement as per GLO Field notes for Contract No. 452, executed by Herman Gradon
- Set steel fencepost on line
- //// Line marked with flagging and paint on adjacent trees

## REFERENCE MATERIAL

- Union County Monumentation Records
- Umatilla County Monumentation Records
- Umatilla County Survey Number 12-144-B
- GLO Field Notes for Contract No. 452, executed by Herman D. Gradon, dated June 16, 1882

## NARRATIVE

This survey was performed at the request of Steve McClelland on behalf of Hancock Forest Management, land manager for the lands within. Mr. McClelland wanted the lines shown hereon marked with paint and flagging for logging purposes. A diligent search for the West quarter corner of Section 33 revealed no evidence of the original corner. I place the corner at proportionate position. I divide the section as per BLM Manual of Instructions 2009. The names shown hereon are internal divisions within the Hancock Forest Management group. I find no other unusual conditions with this survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
JUNE 2, 2010  
JEFFREY S. HSU  
83571

Renewal Date: June 30, 2015

**BAGETT, GRIFFITH & BLACKMAN**  
2006 Adams Avenue, LaGrande, Oregon  
Map of Survey

Situated in Section 33, Township 1 South,  
Range 36 East of the Willamette Meridian

UMATILLA COUNTY

SURVEYED FOR Hancock Forest Management

SURVEYED BY J. S. H.

Scale: 1" = 500' Drawn by: J. S. H. May 2013

RECEIVED BY  
Umatilla County Surveyor  
Date: 5/14/2013  
Rec'd By: J. Hsu  
No.: 12-149-B

