



PURPOSE OF THIS SURVEY WAS TO SHOW AN ADJUSTED PROPERTY LINE BETWEEN PROPERTIES BELONGING TO LORAN AND PATTI MONACO AND THE ATHENA-WESTON SCHOOL DISTRICT. CONTROL FOR THIS SURVEY WAS FROM TIES TO THE MONUMENTS AT MAIN AND HILL STREET AND MAIN AND BROAD STREET AS SHOWN ON THE CONTROL SURVEY OF THE TOWN OF WESTON BY WILLIAM WELLS, PLS 1107.

THE SURVEY WAS TO A LINE AGREED TO BY BOTH PARTIES FOLLOWING AND STRAIGHTENING AN EXISTING FENCE LINE. THE ALLEY THROUGH THE CENTER OF BLOCK 2 HAS NOT BEEN VACATED YET.

BEARINGS HAVE BEEN ROTATED TO TRUE BEARINGS BY ROTATING FROM THE GRID BEARINGS SHOWN ON THE CONTROL DRAWING.

**LEGEND**

- INDICATES SET 5/8" X 30" IRON REBAR WITH ALUMINUM CAP STAMPED PLS 933.
- INDICATES FOUND MONUMENTS FROM CONTROL SURVEY

SURVEY TIES TO MAIN STREET MONUMENTS ●

NW CORNER LOT 7 TO BROAD N 59°35'57" E - 310.70'  
 NW CORNER LOT 7 TO HILL N 64°59'58" W - 355.27'

**RECEIVED BY**  
 Umatilla County Surveyor  
 Date: 3/18/2016  
 Rec'd By: Jay Nelson  
 No.: 16-036-B

<b>KRUMBEIN ENGINEERING LTD.</b> ENGINEERS - SURVEYORS - PLANNERS 361. S.E. Second Pendleton, Oregon	Scale 1" = 20'	Drn. By HP	Drng. No. 1412C	Revision 1
	Date 10-10-14	Ckd. By DMK	Job No. 1332	Revision 2
PROPERTY LINE ADJUSTMENT ATHENA-WESTON SCHOOLS to MONACO BLOCK 2, GEORGE HARTMAN'S ADDITION to WESTON, OR		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Klein</i> EXPIRES JULY 17, 2020 PLS 933		SW 1/4, SECTION 23 TOWNSHIP 4 NORTH RANGE 35 EAST W.M.

RENEWS 6/30/2015