

# BASIS OF BEARING

The Southeast corner of Section 11 to the Northeast corner of Section 2, Township 2 South, Range 35 East of the Willamette Meridian being North 0°02'02" East, as per Survey Number 027-2003

SCALE: 1" = 500'

## LEGEND

- Found monument as described, marked as per Union County monumentation records
- ⊙ Set 2 1/2"x30" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County monumentation records, filed separately
- Set 5/8"x30" iron pin with 2" aluminum cap, marked as per Union County monumentation records, filed separately
- ( ) Record measurement as per field notes of GLO Contract No. 451, executed by Rufus Moore

## REFERENCE MATERIAL

Union County Monumentation Records  
 Survey Number 43-82  
 Survey Number 027-2003  
 Survey Number 030-2008

Field Notes for GLO Contract Number 451, executed by Rufus Moore, dated June 12, 1882

## DEED REFERENCES

Microfilm Document Number 20134220  
 Microfilm Document Number 20045925

## NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager for the land within. Mr. Marolla wanted select corners set in Section 15 prior to logging.

I find and accept the existing monuments as shown hereon. At the Northwest corner of the Section, I find no remains of original GLO evidence. There are three corner location tags on snags as mentioned in corner record filed in Union County Monumentation Records as 10-88R, dated Sept 14, 1987. Origins of this corner record are unavailable. Corner record implies that there was both a fence corner and an original bearing tree at the time. Bearing and distances on location tags appear to converge on a single position. This position is no longer a fence corner, but it is harmonious both in bearing and distance with the NE corner of Section 15 and in bearing with the quarter corner between Section 15 and 16. Because I believe that these location tags represent a perpetuation of the original corner, as well as representing a position of a former line of possession, I accept these tags as the best available evidence.

No remaining evidence could be found at the North quarter corner. I set this corner at proportionate position. Subdivision of the section is as per BLM Manual of Instructions. I find no other unusual conditions with this survey.



### RECEIVED BY

Umatilla County Surveyor  
 Date: 05-31-2016  
 Rec'd By: m. Kelland  
 No.: 16-066-B

<b>BAGETT, GRIFFITH &amp; BLACKMAN</b>	
2006 Adams Avenue, LaGrande, Oregon	
Map of Survey	
Situate in Section 15, Township 2 South, Range 35 East of the Willamette Meridian	
UNION COUNTY, OREGON	
SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 500'	Drawn by: J. S. H. May 2016

