

Nanhole. Elev. Top = 88.10
Elev. Inlet = 80.80

N.W. Cor. 16 13.33 from N.E. Cor.
Iron Pin at N.W. Cor.

590° E.H.
To Nanhole.
3+77.5 Δ 37° 13' R.

End of 8" Water Pipeline
Sta. 0+00 at
S.E. Cor. Tract
60 Ft. Oiled St.
From Pin (cont.)
19' E.
Division Bot. 5+58.
Power Pole 10' E. of P.L.



Trees.

Trees.

SE 10

S.W. Corner - 16 13.33 from S.E. Cor.
Iron Pin at S.W. Cor.

Highland St. Graveled St. Road # 610.

PLAT
OF

Tract of land in SE 1/4 of Section 10,
Township 4 N, Range 28 E, W.M., Oregon. Surveyed
for School District No. 8 Hermiston, Oregon.
November 1951 by H.L. Melton, Registered
Professional Engineer No. 1337, Oregon.

SCALE: 1" = 50'



652

4028 100
Q-1353-B

FIELD NOTES

OF

Survey of Tract of Land in the S.E. 1/4 of Section 10
T 4 N. R 28 E. W. M.

Beginning at a Monument which is an Iron Pin at the S. E. Corner of Section 10, T 4 N. R 28 E. W. M. I ran North on the East Line of Sec. 10 a distance of 330 ft. Thence West and parallel to the South Line of Sec. 10 a distance of 300 ft. to the point of beginning. Thence North along the west side of First Avenue a distance of 5400' where I set an iron Pin; Thence I ran West and parallel to the South Line of Sec. 10 a distance of 1613.33 Feet where I set an iron Pin; Thence I ran South and parallel to the East Line of section 10 a distance of 5400 ft. to a point on the North Line of Highland street where I set an Iron Pin; Thence I ran East on the North Line of Highland street a distance of 1613.33 ft to the point of beginning where I set an Iron Pin.

Tax 103- ~~11~~
Book 202-P-190-

J. L. Melton
Reg. Prof. Error Ore No 1337