



**NARRATIVE:**

A search of county surveyor records found no record of surveys in the old town of Foster. Inspection of the original plat (1883) showed a point which I assumed was the 1/16 corner north of the southwest corner of section 32. I scaled a distance to the northwest corner of block 9 from that assumed 1/16 corner but it was so far from the corner as surveyed I then concluded that the subdivision was never tied to the section corners. There is an old fence which is within 2 feet of the north and west lines of the subdivision as surveyed. Other evidence to support the location of the found monument is that the end of the old bridge over the Umatilla River is very nearly on the centerline of Seymour Street.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*J. Dennis Edwards*  
OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RECEIVED BY  
Umatilla County Surveyor  
Date 6-13-80  
Rec'd By ELC  
No. R-200-B

SURVEY FOR: <b>H.L. MILLER</b>	
LOCATION: <b>BLOCK 9, TOWN OF FOSTER-NOW STANFIELD SW 1/4, SEC. 32, T4N, R29E., W.M.</b>	
DATE <b>6-3-80</b>	SCALE: <b>1"=60'</b>
● MONUMENTS FOUND	(OOO) OF RECORD
○ 1/2" IRON RODS SET	JOB N <sup>o</sup> S 8005087
<b>EDWARDS SURVEYING</b> 567-3336	P.O. BOX 763 HERMISTON, OREGON