

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 61	GEODETIC COOR: NAD 83(91):
SECTION: SW 1/4, S6, T.2N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45° 40' 50.50100" N LONG: 118° 51' 52.87507" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 738500.815 E: 8620033.934 THETA: 1° 09' 35.07"
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	SCALE FACTOR: 0.99993449 ELEV: 1267.65 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
ORDER: SECOND ORDER, CLASS I	CITY OF PENDLETON CO-ORDINATES INT.FT.:
	N: 54561.349 E: 27850.299

LOCATION:

TRAVEL WESTERLY FROM THE ENTRANCE GATE TO THE PENDLETON SANITARY LANDFILL DRIVE TO THE NORTH-SOUTH FENCE LINE. FOLLOW FENCE SOUTH AND THEN SOUTHEASTERLY ALONG 4-WHEEL DRIVE TRAIL DOWN RIDGE TO AN EAST-WEST FENCE LINE. STATION IS SOUTH 35° EAST, 450 FEET M/L.

STATION IS 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "OR PLS 1106, WA PLS 17372"

STATION IS LOCATED IN CRP FIELD AND WILL BE DISTURBED WHEN FARMING RESUMES.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-96*