

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 90	GEODETIC COOR: NAD 83(91):
SECTION: NW 1/4, S7, T.2N., R.33E., UMATILLA COUNTY, OREGON	LAT: 45° 40' 01.05998" N LONG: 118° 44' 43.65085" W STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
DATE SET: EXISTING MONUMENT	N: 734133.639 E: 8650609.201 THETA: 1° 14' 39.47" SCALE FACTOR: 0.99993237 ELEV: 1236.46 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
SURVEYOR: WILLIAM R. WELLS PLS 1106	CITY OF PENDLETON CO-ORDINATES INT.FT.:
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	N: 49542.247 E: 58329.032
ORDER: SECOND ORDER, CLASS I	

LOCATION:

STATION LOCATED WEST OF HIGHWAY 30, 75 FEET M/L WEST OF CENTERLINE OF ROAD, 2500 FEET M/L NORTHWEST OF INTERSECTION WITH I-84. WITNESS CORNER SIGN IS VISIBLE FROM ROAD, SIGN IS ON A 3 FOOT STEEL FENCE POST SOUTH OF CORNER MONUMENT.

STATION IS A 2 1/2" BRASS CAP IN A MOUND OF STONE, WITNESS CORNER, MARKED "W.C., 60.00 FEET, T2N, 1/4S12, R32E;R33E, 1990, PLS 1106". STATION IS REFERENCED BY RECORDED CORNER CERTIFICATE.

THE STATION IS THE WITNESS CORNER MONUMENT 60 FEET SOUTH OF CORNER POINT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-96*