

The combined factor for conversion was determined as follows:

Scale factor at Station "Pendleton" = 0.99993239.

Elevation factor (from City Control Net Map) = 0.9999405.

Matching factor = 1.00000900.

Combined factor, City to State Plane Coordinates = 0.99993239 times
0.9999405 times 1.00000900 = 0.999881893.

Combined factor, State Plane Coordinates to City = 1 divided by
0.999881893 = 1.000118121.

Will. R. Wells

William R. Wells, PLS
March 21, 1996

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-96