

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 82	GEODETIC COOR: NAD 83(91):
SECTION: SW 1/4, S31, T.3N., R.33E., UMATILLA COUNTY, OREGON	LAT: 45° 41' 17.05158" N LONG: 118° 44' 13.47844" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 741875.233 E: 8652583.398 THETA: 1° 15' 00.86" SCALE FACTOR: 0.99993565 ELEV: 1148.39 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	CITY OF PENDLETON CO-ORDINATES INT.FT.:
ORDER: SECOND ORDER, CLASS I	N: 57240.869 E: 60468.200

LOCATION:

LOCATED ON NORTH SIDE OF WILDHORSE ROAD 1 MILE M/L NORTHWEST OF INTERSECTION OF HIGHWAY 11 AND WILDHORSE ROAD 50 FEET M/L SOUTHWEST OF INTERSECTION WITH COUNTY ROAD 979, 6 FEET M/L WEST OF PAVED ROAD AND 2 FEET EAST OF FENCELINE PARALLEL TO ROAD.

MONUMENT IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "OR PLS 1106, WA PLS 17372".

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96