

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9345

QUARTER SECTION: SE

GEODETIC COOR: NAD 83(91)

SEC. 20 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'31.67525" N

DATE SET: JULY ,1993

LONG: 119°20'11.70537" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 783117.991 INT.FT.

E: 8498769.292 INT.FT.

THETA: 0°49'30.279"

TYPE: GPS

SCALE FACTOR: 0.999957009

ORDER: SECOND, CLASS: 1

ELEV: 555.629 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND KELLER ROAD, CONTINUE WEST ON FEEDVILLE ROAD 0.22 MILE TO A CROSS ROAD TO THE NORTH, THEN NORTH ON CROSS ROAD 0.2 MILE TO MONUMENT.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 105 FEET EAST OF CENTERLINE OF ROAD, 40 FEET SOUTH OF WATERWAY, 40 FEET NORTH OF TRAVELED DIRT ROAD.

METERS X 3.2808333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

EXP. 12/31/93