

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9347

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 20 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'23.45171" N

DATE SET: JULY ,1993

LONG: 119°20'45.46125" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 782250.826 INT.FT.

E: 8496390.322 INT.FT.

THETA: 0°49'06.340"

TYPE: GPS

SCALE FACTOR: 0.999956563

ORDER: SECOND, CLASS: 1

ELEV: 551.259 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND KELLER ROAD, GO WEST
ON FEEDVILLE ROAD PAST (2) DIRT ROADS TO THE NORTH, 0.7 MILE.
THEN GO NORTH 12 FEET TO MONUMENT.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 12 FEET NORTH OF CENTERLINE OF FEEDVILLE ROAD, 25 FEET
NORTH AND 10 FEET WEST OF TELEPHONE RISER M41992, 40 FEET NORTH
AND 10 FEET EAST OF POWER POLE NO. 4N 28E.

METERS X 3.2808333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1968
WALTER L. CASWELL
737

Exp. 12/31/93