

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9343

QUARTER SECTION: SE

GEODETIC COOR: NAD 83(91)

SEC. 21 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'34.95052" N

DATE SET: JULY ,1993

LONG: 119°19'06.19470" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 783517.050 INT.FT.

E: 8503404.430 INT.FT.

THETA: 0°50'16.739"

TYPE: GPS

SCALE FACTOR: 0.999957187

ORDER: SECOND, CLASS: 1

ELEV: 578.408 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

TRAVEL NORTHERLY ON HWY. 207 0.25 MILE PAST THE INTERSECTION OF
FEEDVILLE ROAD.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

MONUMENT IS EAST OF THE CENTERLINE OF THE RAILROAD TRACKS WHICH
ARE 100 FEET EAST OF 207. STATION IS 12 FEET EAST OF CENTERLINE
OF THE RAILROAD TRACKS, 100 FEET SOUTH OF 1 RAILROAD MARKER, 100
FEET EAST OF CENTERLINE OF HWY. 207.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter Caswell

OREGON
JULY 8, 1963
WALTER L. CASWELL
737

Exp. 12/31/93