

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9337

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 27 TWP.4 N,RGE.28E  
UMATILLA CO.ORE.

LAT: 45°47'55.01368" N

DATE SET: JULY ,1993

LONG: 119°18'16.27025" W

SURVEYOR: WALTER L. CASWELL  
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP  
13545 NW SCIENCE PARK DR  
PORTLAND, OR. 97229  
(503) 643-1073

N: 779524.345 INT.FT.

E: 8507000.267 INT.FT.

THETA: 0°50'52.144"

TYPE: GPS

SCALE FACTOR: 0.999955034

ORDER: SECOND, CLASS: 1

ELEV: 625.727 US.FT.

ELEV. DATUM: NGVD 29

\*\*\*\*\*  
DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND HERMISTON-HINKLE ROAD, TRAVEL WEST ON FEEDVILLE ROAD 0.35 MILE TO RAILROAD ACCESS ROAD ON WEST SIDE OF RAILROAD TRACKS, THEN GO SOUTHERLY ON RAILROAD ACCESS ROAD 0.5 MILE TO DIRT ROAD TO THE WEST. GO WEST ON ROAD 0.1 MILE TO MONUMENT ON SOUTH SIDE OF ROAD.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 45 FEET SOUTH OF CENTERLINE OF DIRT ROAD.

METERS X 3.28083333333 = U.S. FEET  
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Walter Caswell*

OREGON  
JULY 8, 1966  
WALTER L. CASWELL  
737

*Exp. 12/31/93*