

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9348

QUARTER SECTION: NE

GEODETIC COOR: NAD 83(91)

SEC. 30 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'23.07990" N

DATE SET: JULY ,1993

LONG: 119°21'24.53239" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 782173.822 INT.FT.

E: 8493623.400 INT.FT.

THETA: 0°48'38.632"

TYPE: GPS

SCALE FACTOR: 0.999956543

ORDER: SECOND, CLASS: 1

ELEV: 535.826 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND KELLER ROAD, GO WEST ON FEEDVILLE ROAD UNTIL IT ENDS. THEN, CONTINUE WEST 550 FEET PAST HOUSE ON THE RIGHT AND TELEPHONE RISER ON THE LEFT. TOTAL DISTANCE FROM KELLER IS 1.3 MILES.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 550 FEET WEST, CROSS COUNTRY, PAST END ROAD, 440 FEET WEST OF POWER POLE WITH 3 TRANSFORMERS NO. 4N 8E 19800.

METERS X 3.2808333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

Exp. 12/31/93