

Bonneville Power Administration
Geodetic Control Data Sheet

Station: MJ004 (104)
Project: Wallula-Smiths Harbor-McNary
Section: SE 1/4 15 Township: 5 North Range: 28 East Meridian:
County: Umatilla State: OR USGS Quad: Umatilla, Oregon
Surveyor: M R Heidecke Date Surveyed: July, 2001

Instrument:

The horizontal coordinates and orthometric elevation were established by GPS observations using six Trimble 4000 SSI dual frequency receivers with Compact L1/L2 antennae with ground plane.

Adjustment:

The Basis of Coordinates for this survey is the Oregon State Coordinate System, North Zone, NAD 83 (1998). The horizontal component of the least squares adjustment was constrained by holding NGS Stations B 340 (A), B 502 (B), PENDLETON (B), STANFIELD EAST BASE RESET (B), and BURDEN (B). The vertical component of the least squares adjustment was constrained by holding NGS Benchmarks B 340 (First Order Class II), B 502 (First Order Class II), BURDEN (Second Order Class II), V 203 (Second Order Class II), G 640 (First Order Class I). The elevation for point 106, 201, 249, and 255 were determined by differential leveling from G 640, D 502, E 525 and F 431 respectively and held.

Horizontal Datum: NAD83 (1998) Linear Unit: International Feet
Vertical Datum: NAVD88 Linear Unit: U.S. Survey Feet

<u>Latitude:</u> N 45-54-49.66628	<u>Longitude:</u> W 119-17-11.25490
<u>US State Plane Coordinate System:</u>	Oregon North Zone - 3601
<u>Northing:</u> 821,588.942	<u>Easting:</u> 8,510,975.120
<u>Orthometric Elevation:</u> 473.62	<u>Ellipsoid Height:</u> 402.34
<u>Combined Factor:</u> 0.99996003	<u>Convergence:</u> - 0-51-38
<u>Confidence:</u> 95% Confidence ("1.96 Sigma") Values	
Northing-0.009	Easting-0.007 Elevation-0.104

Monumentation: BPA 3/4-inch Aluminum Cap on 5/8-inch aluminum rod flush with ground.

Stamping: HPP-16, 2000

To-Reach Description:

Begin at Umatilla Post Office, Umatilla, OR. 97882. Drive east on Highway 730, 1.9 miles to intersection of a 12 gravel road to right (south). Drive south on the gravel road 0.2 miles to a cattle guard and the station. The station is 16.3 feet from an east/west fence and 16.6 feet from a north/south fence.

Witness post is a yellow carsonite marker inscribed with BPA logo, bearing and distance to station.

RECEIVED BY
 Umatilla County Surveyor
 Date: 2-02
 Received by: KF
 02-19-9
 J