

TOMKINS LAND SURVEYING, INC.
 20 EAST POPLAR, SUITE 204
 WALLA WALLA WA 99362
 PHONE: 509/522-4843
 FAX 509/522-1902
 email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 1040

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. 1/4 CORNER
 COMMON TO SECTIONS 1 & 2.

DESCRIPTION: 1 1/2" PIPE 4" BELOW THE SURFACE 9 FEET S.E. A FENCE CORNER AT THE NORTH
 END OF COWL STREET.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°56'25.25388" N.

LONG: 118°23'34.34939" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 254795.128 METERS

E: 2663379.269 METERS

N: 835942.021 INT. FEET

E: 8738120.960 INT. FEET

ELEVATION: 307.11 METERS

1007.57 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'39.6"

GRID FACTOR: 0.999985380

SEA LEVEL FACTOR: 0.999951807

COMBINED SCALE FACTOR: 0.999937188

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET



RENEWS 12/31/99

6/17/98