

5N35E19

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 1027

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. CENTER OF SECTION 35.

DESCRIPTION: 2 1/2" BRASS CAP IN A MONUMENT CASE AT THE INTERSECTION OF THE OLD MILTON HIGHWAY AND COBB ROAD.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°57'17.16855" N.

LONG: 118°24'09.83882" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 256377.548 METERS

E: 2662573.468 METERS

N: 841133.688 INT. FEET

E: 8735477.260 INT. FEET

ELEVATION: 286.66 METERS

940.49 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'14.5"

GRID FACTOR: 0.999988814

SEA LEVEL FACTOR: 0.999955015

COMBINED SCALE FACTOR: 0.999943829

CONVERSION:

METERS X 3.2808333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET



RENEWS 12/31/99

6/17/98