

6235 TM

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 906

LOCATION: TOWNSHIP 6 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. 1/4 CORNER
COMMON TO SECTIONS 26 & 27.

DESCRIPTION: RAILROAD SPIKE WITH A PUNCH MARK 0.1' BELOW THE SURFACE OF THE
ASPHALT AT THE INTERSECTION OF WINESAP ROAD AND APPLETON ROAD.

GEODETTIC COORDINATE: NAD 83(91)

LAT: 45°58'09.57210" N.

LONG: 118°24'47.65708" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 257973.875 METERS

E: 2661717.544 METERS

N: 846370.981 INT. FEET

E: 8732669.090 INT. FEET

ELEVATION: 264.49 METERS

867.74 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°28'47.6"

GRID FACTOR: 0.999992345

SEA LEVEL FACTOR: 0.999958495

COMBINED SCALE FACTOR: 0.999950840

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/99

6/17/98