

ROAD No

298.

Road No 298

Report of Viewers. Field Notes and Plat of Survey of a County Road coming at the Eastern end of Front St. in the Town of Foster and ending at N. E. cor. of N. W. 1/4 Sec 12 Sp 3 N. R 29 E. W. M.

Report of Viewers

To the Hon. County Court for Umatilla Co. Oregon.

We the undersigned, viewers on County Road No 298 would respectfully report, that we met with the County Surveyor at time and place appointed by your Hon Body and proceeded to view out and survey said road as by law required, we find the road for the most part located on section lines and upon comparatively level ground, we believe a road may be easily opened and kept in repair; the said road is very much needed by the community surrounding it and would be of great advantage to the general public, for these several reasons we recommend that said road No 298 be declared a public highway, witness our hands this 18th day of August 1887.

Charles Riggs }
J. C. Mendenhall } Viewers
B. F. Raley }

Field Notes of the survey of Road No. 298, for Umatilla Co. Or. met B. F. Raley, J. C. Mendenhall and Char. Riggs, viewers on Road 298, at Foster, Umatilla Co. Or. Aug 16 1887. Robt E. Ward and Jno J. Mendenhall were called to act as chmn. and B. F. Raley as marker, after qualifying each as directed by law, I set initial post in mound at the intersection of the southern line of Front Street with the eastern line of Knowles Street in the town of Foster as described.

I run thence

S 32° 00' E	143	ft	Set angle stake in field E. of traveled road. Turn 9° 00' R.
S 41° 00' E	571	" "	" " " " " " hay rd " 19° 40' R.
S 21° 20' E	1050	" "	" " " " " on knoll E of Baumgardners house " 11° 00' R
S 10° 20' E	2037	" "	" " " " " " Summit " 28° 50' L.
S 39° 10' E	2664	" "	" " " " " " hollow " 13° 20' R.
S 25° 50' E	3235	" "	" " " " " " flat " 22° 50' R
S 3° 00' E	3898	" "	" Intersect line E & W through center Sec 5 S. 3 N R 29 E at pt. 30' east of center of said line, which I find as follows, to wit: I find original witness trees to 1/4 S. cor. bet. Secs. 5 & 6, same Sp. and restore corner, (which see "Record of Surveys" in Co Surveyors office" Sec. 5 S. 3 N. R 29 E subdivided. Request of B. F. Raley et al) I then run true line E & W through center said Sec 5 from 1/4 S. cor. bet. Secs. 5 & 6 to 1/4 S. cor. bet. Secs 4 & 5 and