

Road No 299

Report of Viewers. Field Notes^{and} Plat of Survey of a County Road
beg. at the S.W. cor. of Sec. 6. T⁵ N. R 36 E. W. m. ^{and} ending at the N.E. cor.
of Sec 3 in T⁵ N. R 36 E.

Report of Viewers.

To the Hon. County Court for Umatilla County, Oregon.

We the undersigned viewers on road No 299. for the County
of Umatilla^{and} State of Oregon, would respectfully report that we met
with the County Surveyor on the day^{and} at the place specified in
our notices of appointment as viewers above described, ^{and} pro-
ceeded to view out^{and} survey said road as described in said no-
tices; we find the road located on good ground, excepting about
the last one thousand feet which crosses a gulch^{and} ascends
hill; the road is located on section^{and} subdivision lines^{and} is
very much needed, as it ties two roads^{and} furnishes oppor-
tunity to reach prominent points by a route at least five miles
shorter than the one now necessarily traveled. therefore we
would recommend that the Prayer of the petitioners for road No
299 be granted^{and} that said road be declared a public highway.

Witness our signatures this 27th day of August 1887.

W. S. Frazier

A. M. Elam

P. M. Gerking

} Viewers No 299

Field Notes of Road Survey No 299 for Umatilla Co. Or.

I met A. M. Elam, Peter Gerking^{and} W. S. Frazier, viewers on
County road No 299, at Milton, Or. Friday August 26th 1887. Harvest-
ing rendering a scarcity of laborers, A. M. Elam^{and} Peter Gerking,
chose to act as chainmen^{and} W. S. Frazier as marker, I qualified
each for his particular calling, as directed by law, ^{and} set
initial post in mound 28 feet S.W. of corner for Sec. 1. 6. 7 & 12 on
T⁵ N. line bet. Rgs. 35 & 36 E. T⁵ N.

I run thence (Var. by sun N. 20° E.

East	ft.	On true line bet. Secs. 6 & 7 S. T ⁵ N. R 36 E.
	550	Descend
	850	Ravine N & S - 10'
	2510	1/4 S. Cor. bet. Secs 6 & 7
	5202	Int. N & S line at Cor. for Sec. 5. 6. 7 & 8 Set angle stake 20' south of point. Thence North on true line bet. Secs 5 & 6
	5280	Set 1 m. post 20' East of line, ^{and} continue course.
North	150	Descend
	300	Ravine N.W. - 6'; Ascend
	500	Summit.