

- S 0° 35' W. 45.10 Spring branch 12 links wide runs N. W.  
 53.60 Ascend steep bluff + 50'  
 54.21 S. W. cor. See 14, on steep N. hill side,  
 56.75 Summit; road graded down toward N.  
 69.50 Descend, road in lane on line bet. Sees. 22 & 23  
 74.25 Foot of descent - 30'  
 80.00 Set 1 mile post about 30 links west of point  
 I continue on line between Sees 22 & 23,  
 11.00 M. F. Smith's house, on E. side of lane  
 11.18 Fine Spring on line.  
 20.00 Jas D. Perry's house on W. side of lane.  
 27.00 Enter brush<sup>and</sup> scattering timber along W. W. River  
 28.00 Set angle stake 32 links east of pt. <sup>and</sup>  
 Turn thence 24° 30' Right.
- S 25° 05' W 28.40 Blough 22 links wide runs N. W.  
 31.18 Cut A on round fence post 6 lks. west of pt. <sup>and</sup>  
 Turn 29° 30' Left
- S 4° 25' E 35.71 Set angle stake against fence 13 lks. west. <sup>and</sup>  
 Turn 6° 25' Left
- S 10° 30' E 39.00 Set angle stake 30 links east, against N. Ford's fence  
 on reputed See. line bet. Sees. 22 & 23. This point  
 is 3 links east of a Cottonwood tree 2 ft. dia. <sup>and</sup>  
 notched with three notches on opposite sides  
<sup>and</sup> in direction of the road.  
 Turn thence 11° 30' Right
- S 0° 40' W 40.28 Walla Walla River 32 links wide runs N. W.  
 Enter lane N & S on land of A. Moran, deceased  
 51.32 Along lane <sup>and</sup> 20 ft west of N. Ford's fence on reputed  
 line bet. Sees 22 & 23. Set angle stake 30 links E against  
 N. Ford's fence, <sup>and</sup>  
 Turn thence 42° 00' Right
- S 42° 40' W 52.90 Set angle stake in bunch of Elders on W. bank of river  
 30 lks E. Turn thence 46° 30' Left
- S 3° 50' E 56.73 Set angle stake 30 lks east of pt. on N. side of fence runs S & W.  
 Turned thence 2° 30' Right
- S 1° 20' E 66.47 Set angle stake 30 links east of point, <sup>and</sup>  
 Turn 9° 45' Left
- S 11° 05' E 67.45 W. W. River 30 links wide, runs N. E.  
 68.54 Int. reputed line bet. Sees 26 & 27; Set angle stake  
 at fence cor. 6 links E. <sup>and</sup>  
 Turn on line bet Sees 26 & 27 (This point is 638 links North  
 of witness cor. which is a dead willow 6 in. dia. marked  
 on N. W. blaze AM CC <sup>and</sup> on S. W. blaze W B CC