

on the 15<sup>th</sup> of June, I set the following described corners, to wit:  
 S.W. cor. Sec 15 T 6 N R 34 E, a basalt stone, 3 notches on E & S faces; a poplar 8"  
 dia. 190 lks north. 1/4 S. on S. side said Sec. 15, a porous basalt stone 13" x  
 9" x 8, marked 1/4 on N. face. 40 lks. N. of slough, 1/4 S. on E. side said Sec 15, a  
 granite stone 13" x 10" x 6", marked 7/4 on W. face 585 links S. of branch. 1/4 S. on W.  
 side said Sec 15, a granite stone 15" x 13" x 10", marked 7/4 on W. face, in W. side  
 of ditch N. & S. Center of said Sec. 15, a basalt stone 13" x 15" x 10" marked C.S. 15  
 on South face.

I set initial post for Road No 308, a sawed fir 4" x 4" x 4" in mound of  
 earth 4' square at base <sup>and</sup> 2' high, post marked R on E. face, <sup>and</sup> run, thence,  
 on true line East through center Sec. 15 T. 6 N. R. 34 E.

39.56 Int. line bet. Secs 14 & 15 at 1/4 S. cor

cut A on fir post in ditch <sup>and</sup> wire fence, course NYS

39 links S. of 1/4 S. cor <sup>and</sup> turn to cross small branch

N 4° 45' E 45.57 center small branch 25 links wide, course about west,

49.07 set angle stake 45 links west of Pt. <sup>and</sup> Turn to intersect line bet. D &

W. J. 76° 30' Right

N 81° 15' E 62.96 Intersect N. bndy of Oregon; set terminus a sawed fir 4" x 4" x 4" marked

R on S.W. face in mound of earth 4' x 4' at base <sup>and</sup> 2' high, on knoll.

I hereby certify that the foregoing notes of the survey of Road  
 No 308, for Umatilla Co. Oregon are correct.

Jno C. Arnold, County Surveyor

Plat of Road No 308, Umatilla County, Oregon  
 Township 6 N, Range 34 E, W. M.

7	8	9	10	11	12
13	17	16	Road 308 Initial point	14	13
19	20	21	22	23	24

I hereby certify that the accompanying plat of  
 road survey No 308 for Umatilla County, Oregon  
 is correct.

Journal H, page 77

" H. " 947

Road Granted July 11 " 1888

Recorded Oct 11 " 1888

G.A. Hartman, Co Clerk

By J.N. Parker, Deputy.

Jno C. Arnold

County Surveyor

County  
 on State  
 County  
 places  
 on said  
 titioners  
 line  
 division  
 as an  
 to north  
 would  
 highway  
 our  
 ing of  
 ad Jo<sup>s</sup> E.  
 ne away,  
 ich is in  
 quarters,  
 rriers  
 notes of  
 find cen-  
 he four  
 by right  
 completing  
 of June 12"  
 ch to ach  
 Umatilla  
 nan to carry  
 each quali-  
 as com-  
 y No. 309.