

ROAD NO

310.

## Road No 310.

Report of Viewers. Field Notes and Plat of Survey of County Road  
Beg. at 1/2 mile stake on S. line of Sec 17 & 4 N. R 33 E and running W. to Sec cor  
of Sec 18 same T & R. North 1/2 mile to 1/2 mile stake on W. line of said Sec  
18 to connect with County Road.

## Report of Viewers

Pendleton, Umatilla County Or. May 7<sup>th</sup> 1888.

To the Hon County Court, Umatilla Co. Or.

We your viewers on County road No 310 would respectfully  
report that we, in connection with County Surveyor Jno C. Arnold  
proceeded to view out and survey out said road 310 as ordered in our  
several notices of appointment; we find the road located on com-  
paratively good ground, wholly upon section lines and a road much  
needed, we therefore recommend that said road be declared a public  
highway and the prayer of petitioners for County road No 310 be granted.

Witness our hands date as above

W. M. Scott

John Caplinger

G. W. Knight

## Field Notes

of the Survey of Road 310 Umatilla Co Or.

I met the viewers on road survey no 310 for Umatilla  
County Or. and administered oath to each, at the time and place ap-  
pointed for the same, and calling to our aid James B. Kennedy and J. E. Mc-  
Coy to act as chain carriers, and J. E. McCoy to act as marker, I admin-  
istered the usual oath of such assistants respectively.

I set initial post, fir 4x4 ins. 4 ft long marked R on W. face, and  
in earth mound 4 ft sq. and 2 ft. high N 51° 30' E from 1/4 Sec. Cor. bet. Secs.  
17 & 20 T 4 N R 33 E, and run thence W. along road in lane, purporting  
to be on line bet. said Secs 17 & 20. var. 20° E

chs.

10.00 Ravine, course North; ascend

20'

17.00 Summit

39.75 Cor. for Secs. 17, 18, 19 & 20. I turn 2° R. along line purporting to  
be true line bet. Secs. 18 & 19, along road in lane

N 88° 00' W

54.75 Ravine runs North

20'

68.50 " " about S 25° W; ascend

30'

79.40 Fences run N 45 on opposites of lane E & W

80.00 Set sawed fir post 4x4 ins. 4 ft long marked IM on north face  
in mound of earth 4 ft square at base and 2 ft. high on south  
side of lane. Course E & W. and 58 links wide at Pt.

I turn 3° 30' L. along line purporting to be true W. 1/2 of  
line bet. Secs. 18 & 19, road in lane

S 88° 30'

N 1° 30' W