

ROAD NO  
312.

Road No 312

Report of Viewers. Field Notes and Plat of Survey of a County Road  
Sec. 25 T. 4 N. R. 31 E. and  
ending at intersection with County Road No 205.

Report of Viewers

To the Hon. County Court, Umatilla County Oregon.

We, your viewers on County road no. 312, respectfully report that we  
met at time and place appointed for the same, and with Geo. C. Arnold Co.  
Surveyor, proceeded to view out and survey said road, conformably to your  
orders. We find the road located on section and half section lines through-  
out its whole length, and upon comparatively good ground; it is also in  
a vicinity where roads are "few and far between" and would be of great  
convenience to the general public; the road, if granted, will be com-  
paratively easy to open and keep in repair; we would, therefore, recom-  
mend that the prayer of the petitioners for County road no 312 be granted.

J. W. Williams } Viewers for Road 312  
Philip A. Wild } Umatilla Co. Oregon.  
Evert J. Meiners }

Field Notes

of Road Survey No 312, Umatilla Co Oregon.

I met J. W. Williams, P. A. Wild and E. J. Meiners for County Road no 312,  
Boards of viewers, and calling J. E. McCoy and Saml. A. Crowell to assist in chaining  
and marking, I qualified each by administering the usual oath in such  
cases, and commencing at 1/4 S. Cor. bet. Secs 24 & 25 T. 4 N. R. 31 E. W. M. I measure  
North, va. 21° and set temp cor. at a distance of 13.50 chs. I set initial post  
marked R on S. face 45 links N. of Pt. and run thence South on line purporting  
to be true line N. & S. through center of sections 24 & 25, as above described; the  
said N. & S. center line indicated by lines of fencing. var. 21°

	chs	ascend	
South	13.50	1/4 S. Cor. bet. Secs 24 & 25 T. 4 N. R. 31 E.	
	14.00	Summit; Descend	+ 50'
	15.00	Ravine N. W.; Ascend	- 8'
	41.00	Summit.	+ 60'
	55.00	Descend.	
	59.50	Ravine runs W.; Ascend	
	80.00	Set 1 mile post 30 lks. West of Point.	
	5.00	Summit	
	12.87	1/4 S. cor bet. Secs. 25 & 36, set angle stake 30 lks. E. of Pt. and 89° 45' R. along true line bet. said Secs 25 & 36	
589° 45' W.	52.61	Cor. for Secs 25, 26, 35 & 36. set angle stake 30 lks. W. and turn 95° L along reputed line bet. Secs. 35 & 36	
S 5° 15' E	63.30	Ravine Course N. W.; ascend	- 8'
	73.50	Summit; Descend	