

ROAD No

316

Road No. 316

Report of Viewers, Field Notes & Plat of Survey of a County Road Beg. at a pt on the Co. Road running E. & W. on the Sec. line bet. Secs. 22 & 15 Tp. 5 N. R. 34 E. W. M. at Middle of said Sec line & ending at a point on the Co. Road in the middle of Sec 35 Tp. 5 N. R. 34 E. W. M.

- Report of Viewers -

To the Hon. County Court Umatilla County, Or: -

We, the undersigned, Viewers on Road Survey No. 316 for Umatilla Co. Oregon would respectfully report that we met Jno. C. Arnold, County Surveyor within five days of the time appointed, & at the place appointed for the same, & after being qualified, as required by law, we proceeded to view out, survey & locate Road No. 316 as prayed for in petition for the same; calling to our aid J. M. Jarvis & Wm. A. Raymond to act as chainmen, & Adam Crim to act as marker who were each properly qualified.

We find the said Road 316 very much needed, located on comparatively good ground, & now in tolerable condition & much traveled.

We have set angle points along on the Eastern boundary of the O & W. & Right of Way, merely for the purpose of denoting the extreme Western limit of the said road 316, where necessary, & the said road 316 is located entirely east of & free from said R. R. Right of Way.

We would recommend that said road 316 be declared a public highway.

Witness our respective hands, at Waterman Station this Seventh day of December A. D. 1888

Filed Jan. 5<sup>th</sup> 1889  
G. A. Hartman, Clerk

E. T. Wormley  
Jackson Nelson.

- Field Notes -

Road Survey No. 316 Umatilla Co. Oregon.

I met Jacob Nelson & Sol Wormley, Viewers on Road Survey No. 316 for Umatilla County, Oregon, at the place appointed for the same, on the 8<sup>th</sup> day of Dec., A. D. 1888,

I called Adam F. Crim to act as marker & J. M. Jarvis & Wm. A. Raymond to act as chainbearers, & administered to each of the viewers & assistants the usual oath of qualification.

I find stone, in mound, in N side of traveled road in lane E. & W. said stone purporting to mark 7 S. Cor. bet Secs. 15 & 22 T. 5 N. R. 34 E. I, therefore, set initial post against fence on N. side of lane, & 35 links West of Cor. Stone, from which I run South, along center of road in lane.

Var. 18° E < Dense fog & freezing - needle somewhat affected, & imperfect in registration >

25.53 Cattle guard on E. side O. & W. T. R. R. track

26.30 A point 75 links East of center said R. R. track

Drove an iron tie pin at point & set A on East & South faces of East post in Cattle guard; thence

38.50 along Eastern line of R. R. Right of Way, W. Raymonds house bears West about 300 links.

80.00 Set 1/4 mile Post, 120 links East of Center R. R. track.

S 24° 30' E

S 27° 30' E

S 34° 30' E

East

S 12° 00' E

S 42° 00' E

S 2° 15' E

File  
82