

above speci-
in my of

70 on West
30 E. from
links distant

accord with
decided this
set side

ch I leave

line bet. Secs.

West	28.96	Reputed center Sec. 11	
		Set angle Post at pt.,	From thence
North		on line N & S. through center Sec. 11	
	35.00	Set angle post at pt	" "
S. 80° 50' W	48.50	Ascend.	
	56.50	Ravine - 10' runs West	
	58.66	Set angle post at pt.	" "
N. 72° 43' W	65.50	" " " " "	" "
N. 88° 00' W	77.75	Int. line bet. Secs 10 & 11 Set angle post at pt., Turn on said Sec line.	
South	80.00	Set 4 M post 30 links West of pt.	
	7.38	1/4 S. Cor. bet. Secs 10 & 11; Ascend	
	30.00	Summit.	
	48.43	Cor. for Secs 10, 11, 14 & 15.	
	78.50	Ravine - 10', runs N. W	
	80.00	Set 5 mile post 30 links East of pt.	
	7.50	1/4 S. Cor. bet Secs 14 & 15	
	80.00	Set 6 Mile post 30 links East of pt.	
	6.44	1/4 S. Cor. bet Secs 22 & 23	
	41.00	Descend hill	
South	47.47	Cor. for Secs. 22, 23, 26 & 27	
	53.00	Ravine - 6, runs S. W.	
	80.00	Cut 7 M on East side of larch post, 20 links west of pt., in fence N. & S.; raised mound about post.	
	3.50	Set angle post at pt. & turn, thence.	
S. 83° 05' E.	43.75	Center Sec. 26	
	49.50	Set angle post at point, & turn, thence	
S. 28° 35' E.	57.40	" " " " " " " "	
S. 45° 45' W.	72.00	Ravine - 8', runs N. W.	
	80.00	Set 8 mile post 30 lks N. of Pt	
	12.00	Ald furrow E. & W. = line bet Secs 26 & 35	
	16.02	Set angle post at pt., & turn, thence.	
S. 69° 30' W	23.92	" " " " " " " "	
S. 13° 53' W	33.06	" " " " " " at intersection of N. side Alkali	
		Canon; turn, thence,	
S. 31° 45' E	53.72	Set angle post at pt., & turn, thence,	
S. 24° 36' E	78.68	" " " " " " "	
S. 29° 35' E.	80.00	Cut 1x M on basalt stone 35 x 20 x 15 ins., 30 lks, N of pt.	
	32.20	Set angle post at pt., & turn, thence	
S. 33° 55' E	47.50	Water Channel in Alkali Canon.	
	52.50	Set post terminus at pt. (Raining like - much)	

This Road is 60 feet wide, although the mile posts are but 30 links to one side of the line. The posts are all of the dimensions & are mared & set in ground as required by law.