

Field Notes of Road Survey No 344 for
Umatilla County Oregon,

I meet Jno. L. Stockman and Geo. B. Clark viewers at A. B. Reicks house Aug 4 1890. We call Edgar Thomson and Jno. L. Stockman to chain and mark; each viewer^d assistant was sworn according to law in such case provided. (Initial Post set 30' East of point of commencing.)

I commence 618 ft south of accepted center of Sec 14 T5 NR 32 E and run along fence purporting to be on 1/2 sec line, Ascend. Var 22° E.

- | | | |
|-------------|------|---|
| North | 618 | Center Sec 14 T5 NR 32 E. |
| | 800 | Summit. |
| | 1200 | Head of Ravine SE |
| | 2300 | Set angle post by wire fence N S ^d and turn thence |
| N 75° 45' W | 2635 | " " " and turn right 78° 10' |
| N 2° 25' E | 3350 | " " " " left 54° 48' |
| N 54° 25' W | 3671 | Int. Sec line bet. secs 11 + 14 about 30 rods W of sec cor.
Set angle post by wire E + W and turn on sec line. |
| West | 4000 | Descend. |
| | 5280 | Set 1 m post 30' south of line in Isaac Atkinson's field |
| | 178 | Ravine NW. Ascend. |
| | 387 | Summit. |
| | 487 | Cor to secs 10-11-14+15. Set angle post at cor and turn on line
bet secs 10 + 11. Var 22° |
| North | 850 | Foot of descent |
| | 2050 | Set angle post by N + S fence and turn down ravine. |
| N 25° 12' E | 4481 | " " " 13' N of traveled road NW SE and turn |
| N 28° 20' W | 5007 | " " " do " " |
| N 87° 04' W | 5280 | " 2 m. post 30' West of line. |
| | 300 | Set angle post and turn 22° 15' left. |
| S 70° 41' W | 650 | Int line bet Secs 10 + 11. Set angle post and turn on sec line. |
| North | 1183 | Old road post on south bank of Juniper Canon 85 yards N. E. of School
House. Road up and down Canon. I set Lermimus 30 ft. E on N
side of road in lane E + W. |

Thursday Aug 5th 1890

I hereby certify that the foregoing are the correct notes of
Road Survey No 344 for Umatilla County Oregon.

Jno. L. Arnold
Surveyor.

Filed Aug. 19th 1890
W. M. Pierce Clerk.