

We called to our aid Edgar Thomson } chainmen
 Henry Zahner }
 Same parties Marker
 W^m Jurell, to flag, drive team and
 generally assist.

who were by the Surveyor, each, duly sworn. We viewed, surveyed and located said Road No. 367 as specified in our order. We find the road located upon good ground, for about five miles, identical with road 368. We therefore recommend that said Road No. 367 be declared a public highway and that the prayer of the petitioners for the same be granted.

Witness our respective hands at Pendleton, Oregon, this 30th day of August 1891.

Burr Johnson }
 G. E. Bean } Viewers Road Survey No. 367.
 L. Reith }

Filed Sept. 8th 1891,
 W. M. Pierce Clerk.

Field Notes of Road Survey No. 367 for Umatilla Co. Oregon.

I met Burr Johnson and Louie Reith at Athena Aug. 12th 1891 and administer usual oath of road viewer to each. We call Edgar Thomson and Henry Zahner to chain and mark and administer oath to each.

I set initial post in Road Survey No. 367, 30 feet east of the south end of a bridge across Wild Horse Creek near the center of Sec 34 T 4 N R. 34 E Wm., and from center of south end of said bridge, with a common open sight field compass, I run through center said sec. 34.

South	2260	To 1/4 Sec. Cor. bet. Secs 3+34 T 4 N R. 34 E.
	2434	bet angle post 1, on west side of R. R. thence
S 33°-00' W.	5218	" a. p. 2, in line with center of Commercial Street in the town of Adams, thence in line with said street center.
West	5290	Set 1 mile post 37 South.
	797	Center of W. H. Creek 50 wide, runs S. W. bridged.
	1781	Intersect Main Street center in said town. Set a. p. 3. and turn along center Main Street
South	3525	Center of same creek, course S. W. bridged.
	4695	Set a. p. 4. 80 west of R. R. track and run thence

N
 N 43
 N 53
 N 25
 S 70
 N 55