

Survey of Road No 377 for Umatilla County, Oregon Oct. 17 1891.
Under direction of Geo. Todd, Henry Fry & W.C. Belts,
viewers and assisted by D.S. Morgan and J.C. Hill Chmn. Geo.
Todd, axman and J.C. Hill marker,

I set initial post for R. 377, which is a bearing tree to the
Cor. for secs. 1-2-11-12 of SR. 35E and is 42 links SW of the cor.,
as stated, marked facing the cor. of SR. 35E, $\odot 2$ B and on
west R.O. 377. Raised slight mound of earth around the roots of
tree. With an old Gurley transit, I run $\cup a 20^{\circ} E$
on line bet secs. 2 + 11 Descend,

West	6.50	Set a p. 1 and turn R 2° .
N $88^{\circ} 00' W$	9.50	Center of ravine, course NE, bridged 70 lks across.
	10.00	Cabin bears $\odot 35$ links dist. Ascend.
	12.88	cut A on N side of pine 6 ins dia = a p. 2 and turn R $35^{\circ} 35'$
N $52^{\circ} 25' W$	18.40	" " " " " larch 4 " " 3 " " $L 56^{\circ} 18'$
S $71^{\circ} 17' W$	28.00	Set a p. 4 and turn R $18^{\circ} 30'$ on line bet. secs 2 + 11.
	33.00	Summit of ridge, falls gently north.
	42.20	The \odot Sec. cor. bet secs 2 + 11. Descend
	61.89	" \odot " " on W $\frac{1}{2}$ of line bet. secs 2 + 11.
	80.00	Set 1 m. p. which is a pine 8 ins dia. 47 links N of line, marked / m on south side.
	2.45	The cor. to secs. 2-3-10-11 continued on line bet. secs 3 + 10
	8.50	Swamp 100 lks. wide, bridged. Ascend.
	15.00	Old toll road, nearly N + S.
	15.50	A pine 5 ins. dia bears N of line 45 lks. which I mark R 377 on E for terminus.

I hereby certify that the foregoing are the correct notes of
Road Survey No 377 for Umatilla County, Oregon

Geo. E. Arnold
Surveyor.

Filed Nov. 2 1891
W. M. Pierce Clerk
J. E. Beam Deputy.