

City Oregon  
 Madison  
 Cr.  
 all  
 to mark  
 ending  
 ed to the  
 wing.  
 -30  
 line bet.  
 west,  
 timber  
 N.W. + S.E.  
 g N. + S. said  
 Sec. 30. as  
 U.  
 gh Sec 30.  
 ontig to be  
 ed. 4  
 30 30 lks. E. of line  
 Co. E. of line  
 ist.  
 - Second.  
 f Stone  
 re '116 Sec.  
 r Sec. 30  
 and.  
 as  
 line.

Course	Dist chs	Δ	Remarks
South	57.00		A dwelling house bears E. of line 46 lks. dist.
	59.05		Fence bears E + W.
	75.65		A fir tree 10 ins. dia. blazed on N. S. E. W sides.
	80.00		claimed to be center Sec. 31 - Summit - Second.
	3.13		A tamarack 4 ins. dia. bears east of line 35 lks.
	10.00		dist. marked 2 M. for 2 mile post.
	10.60		Enter field - Fence E. + W.
	11.57		Water in ravine runs S.W.
S. 51° 10' E.	13.37	S. 51° 10'	A fine spring of water. bears west of line 2 lks.
S. 83° 50' E.	22.97	S. 31° 40'	dist; also house bears E about 50 lks. dist.
	30.05		Leave field
S. 0° 40' E.	30.54	R. 83° 10'	Set a. p. mkd 7
	36.55		Cut 8 on pine 24 ins. dia. on line on S hill side
	39.12	R. 72° 05'	Thursday June 2 <sup>nd</sup> 1892.
S. 71° 25' W.	41.56	S. 56° 30'	Pine Creek 15 lks. wide runs S.W. Ascend
S. 14° 55' W.	46.96		Set a. p. on line and cut 9 on fir 20 dia 6 lks north.
	47.98	S. 79° 55'	Brook 4 lks. wide runs N.W.
S. 15° 00' E.	49.04	S. 31° 15'	Set a. p. on line, and cut 10 on fir 5 ins. 8 lks. west
S. 46° 15' E.	55.59	R. 46° 15'	" " " " and cut 11 on spruce 8" dia. 5 lks. east
South	59.64	R. 70° 10'	cut, blazed line E + W. 25 chs. West of cor. to Secs. 5 + 6
S. 70° 10' W.	61.30	S. 108° 15'	on line bet. Ips 3 + 4 N. R. 37 E.
S. 34° 05' E.	64.08	R. 38° 05'	Set a. p. on line, and cut 12 on fir 10 ins. dia. 6 lks. west.
South	80.20		" " " " " " 13 " " 8 " " 17 " north
	10.29		" " " " " " 14 - maple 4 " " 9 " "
	12.10		on '14 Sec. line through E. 1/2 of Sec. 6.
			Set a. p. on line, and cut 15 on fir 6 ins. dia. 4 lks. W. of line
			" " " " " " 16 " " 8 ins. " 12 " S. " "
			" " " " mkd. 17
			A fir 6 ins. dia. bears east 32 lks. dist.
			marked 111 M for 3 mile post.
			a post 4 x 4 x 6 above ground, purporting to be
			'116 Sec. cor. on E. 1/2 of E. + W. Center of Sec. 6.
			intersect road 337 on line E. + W. through center
			of Sec. 6. J. 3 N. R. 37 E.
			I find, here, a post driven even with ground
			surface, which. it is claimed, was driven
			in the survey of road 337. to mark 3/4 mile
			point E. of '14 Sec. cor. on W. body. of Sec. 6.
			as described.
			a stump bears S 72° 40' E 33 lks. dist. marked 18
			From point of road intersection,
			run along center of Road 337.